28/99

TIP NO. B-3530 - INDEX OF SHEETS

SHEET NO.	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, ROADWAY STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
1-C	CENTERLINE COORDINATE LIST
2-2A	TYPICAL SECTIONS, PAVEMENT SCHEDULE
2B	DETAIL OF OFF-SITE DETOUR RESURFACING
2C-2D	REINFORCED BRIDGE APPROACH FILLS
2E – 2H	GUARDRAIL INSTALLATION
2I-2J	STRUCTURE ANCHOR UNITS, GUARDRAIL ANCHOR UNIT, TYPE III
3	SUMMARY OF QUANTITIES
3A	LIST OF PIPE, ENDWALLS, ETC. (FOR PIPES 48"& UNDER)
3B	SUMMARY OF EARTHWORK, SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL, GUARDRAIL SUMMARY
4	PLAN SHEET
5	PROFILE SHEET
TCP-1 THRU TCP-6	TRAFFIC CONTROL PLANS
EC-1 THRU EC-4	EROSION CONTROL PLANS
SIGN-1 THRU SIGN-3	SIGNING PLANS
UO-1 THRU UO-2	UTILITIES BY OTHERS PLANS
X-1	CROSS SECTION SUMMARY SHEET
X-2 THRU X-6	CROSS SECTIONS
S-1 THRU S-21	STRUCTURE PLANS

PROJECT REFERENCE NO. SHEET NO. B-3530 I-A

PAGE 1

GENERAL NOTES:

2002 SPECIFICATIONS EFFECTIVE: 01-15-02

REVISED: 05-14-03

GRADE LINE: GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD ${f II}$.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT AND EARTH SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

UNDERDRAINS:

UNDERDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.03 AT LOCATIONS DIRECTED BY THE ENGINEER.

DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH DETAILS IN PLANS AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE:

BELLSOUTH TELECOMMUNICATIONS - TELEPHONE, TIMEWARNER CABLE-CATV,

PROGRESS ENERGY OF THE CAROLINAS - POWER

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

EFF. 01-15-02

ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January 15, 2002 are applicable to this project and by reference hereby are considered a part of these plans:

DIVISION 2 - EARTHWORK

200.02 Method of Clearing - Method II

225.02 Guide for Grading Subgrade - Secondary and Local

225.05 Method of Obtaining Superelevation - Divided Highways

DIVISION 3 - PIPE CULVERTS

300.01 Method of Pipe Installation - Method 'A'

DIVISION 5 - SUBGRADE, BASES AND SHOULDERS

560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I

DIVISION 8 - INCIDENTALS

806.01 Concrete Right-of-Way Marker

806.02 Granite Right-of-Way Marker

815.03 Pipe Underdrain and Blind Drain

838.01 Concrete Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew

838.11 Brick Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew

840.29 Frames and Narrow Slot Flat Grates

840.35 Traffic Bearing Drop Inlet - for Cast Iron Double Frame and Grates

840.46 Traffic Bearing Precast Drainage Structure

840.66 Drainage Structure Steps

846.01 Concrete Curb, Gutter and Curb & Gutter

862.01 Guardrail Placement