RD203023

COMPUTED BY: BPS DATE: 05/19/03
CHECKED BY: GSB DATE: 04/27/04

PROJECT NO.	SHEET NO.
U-3302	3-B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

Station	Station	Uncl. Excav.	Embank. __%	Borrow	Waste
-Y1- 16+17.01	-Y1- 21+19.34	50	10		40
-LPD- 6+10.05	-LPD- 7+72.65	64	67	3	
-RPD- 5+92.65	-RPD- 10+66.05	541	184		357
SUBTOTAL:		655	261	3	397
WASTE IN LIEU OF BORROW:				-3	-3
GRAND TOTALS:		655	261	0	394
SAY:		700 CY			

UNDERCUT EXCAVATION = 500 CY

SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SY
-Y1-	16+27	16+86	LT	78
			TOTAL:	78 SY
			SAY:	90 SY

SUMMARY OF EXISTING CONCRETE PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SY
-LPD-	6+42	11+28	RT	1,027
-LPD-	6+42	7+37	LT	104
-LPD-	9+45	11+39	CL	2,005
RAMP TO WOODFIN ST.				831
			TOTAL:	3,967 SY
			SAY:	3,980 SY

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".