

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201012

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description		
0000100000-N	800	Lump Sum		MOBILIZATION																	
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING																	
0043000000-N	226	Lump Sum		GRADING																	
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	4508000000-E	SP	612	LF	RESET WATER FILLED BARRIER	5270000000-N	SP	2	EA	GENERIC LIGHTING ITEM FOUNDATION COVER	7684000000-N	1750	3	EA	SIGNAL CABINET FOUNDATION		
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	4510000000-N	SP	20	HR	POLICE	5270000000-N	SP	16	EA	GENERIC LIGHTING ITEM HM LUMINAIRE 400W W/ GLARE SHIELD	7688000000-N	SP	3	EA	CABINET BASE ADAPTER		
0080000000-E	SP	200	TON	CLASS IV SUBGRADE STABILIZATION	4650000000-N	1251	64	EA	TEMPORARY RAISED PAVEMENT MARKERS	5270000000-N	SP	7	EA	GENERIC LIGHTING ITEM LGT STD W/ BREAKAWAY BASE	7756000000-N	1751	3	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)		
0196000000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION	4685000000-E	1205	756	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5270000000-N	SP	7	EA	GENERIC LIGHTING ITEM POST-TOP LGT W/ BREAKAWAY BASE	7780000000-N	SP	17	EA	DETECTOR CARD (TYPE 2070L)		
0318000000-E	300	25	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	4686000000-E	1205	1,488	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5270000000-N	SP	7	EA	GENERIC LIGHTING ITEM REMOVE LGT STD	7960000000-N	SP	8	EA	METAL POLE FOUNDATION REMOVAL		
0366000000-E	310	208	LF	15" RC PIPE CULVERTS, CLASS III	4695000000-E	1205	313	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	5270000000-N	SP	30	EA	GENERIC LIGHTING ITEM STANDARD FOUNDATION POST-TOP, TYPE RIS	7972000000-N	SP	8	EA	METAL POLE REMOVAL		
0720000000-E	310	4	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4697000000-E	1205	720	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	5270000000-N	SP	7	EA	GENERIC LIGHTING ITEM RELOCATE EXISTING WATER METER	7980000000-N	SP	4	EA	GENERIC SIGNAL ITEM DECORATIVE SIGNAL PEDESTAL WITH FOUNDATION		
1121000000-E	520	200	TON	AGGREGATE BASE COURSE	4710000000-E	1205	169	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	5648000000-N	1510	1	EA	TEMPORARY SILT FENCE	7980000000-N	SP	10	EA	GENERIC SIGNAL ITEM DECORATIVE SINGLE MAST ARM WITH METAL POLE		
1297000000-E	607	2,500	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	4721000000-E	1205	4	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	6000000000-E	1605	500	LF	TEMPORARY SILT FENCE	7980000000-N	SP	4	EA	GENERIC SIGNAL ITEM DECORATIVE SIGNAL HEAD - NO PUSHBUTTON (12", 1 SECTION)		
1489000000-E	610	515	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4725000000-E	1205	22	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A	7980000000-N	SP	4	EA	GENERIC SIGNAL ITEM POWDER COAT FOR PEDESTRAIN PEDESTAL		
1498000000-E	610	860	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4810000000-E	1205	6,297	LF	PAINT PAVEMENT MARKING LINES (4")	6009000000-E	1610	100	TON	STONE FOR EROSION CONTROL, CLASS B	7980000000-N	SP	4	EA	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE		
1519000000-E	610	1,380	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4820000000-E	1205	2,066	LF	PAINT PAVEMENT MARKING LINES (8")	6012000000-E	1610	110	TON	SEDIMENT CONTROL STONE	7980000000-N	SP	10	EA	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE		
1560000000-E	620	146	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4835000000-E	1205	338	LF	PAINT PAVEMENT MARKING LINES (24")	6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING							
2264000000-E	840	0.367	CY	PIPE PLUGS	4840000000-N	1205	8	EA	PAINT PAVEMENT MARKING CHARACTER	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING							
2286000000-N	840	7	EA	MASONRY DRAINAGE STRUCTURES	4845000000-N	1205	46	EA	PAINT PAVEMENT MARKING SYMBOL	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING							
2308000000-E	840	7	LF	MASONRY DRAINAGE STRUCTURES	4845000000-N	1205	46	EA	PAINT PAVEMENT MARKING SYMBOL	6030000000-E	1630	125	CY	SILT EXCAVATION							
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4860000000-E	1205	220	LF	REMOVAL OF PAVEMENT MARKING LINES (8")	6036000000-E	1631	570	SY	MATTING FOR EROSION CONTROL							
2374000000-N	840	1	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4870000000-E	1205	84	LF	REMOVAL OF PAVEMENT MARKING LINES (24")	6042000000-E	1632	300	LF	1/4" HARDWARE CLOTH							
2396000000-N	840	2	EA	FRAME WITH COVER, STD 840.54	4905000000-N	1253	64	EA	SNOWPLOWABLE PAVEMENT MARKERS	6042000000-E	1632	300	LF	1/4" HARDWARE CLOTH							
2407000000-N	840	1	EA	STEEL FRAME WITH TWO GRATES, STD 840.37	4935000000-N	1267	35	EA	FLEXIBLE DELINEATORS (CRYSTAL)	6084000000-E	1660	1.5	ACR	SEEDING & MULCHING							
2549000000-E	846	1,090	LF	2'-6" CONCRETE CURB & GUTTER	4945000000-N	1267	5	EA	FLEXIBLE DELINEATORS (CRYSTAL & RED)	6087000000-E	1660	1	ACR	MOWING							
2591000000-E	848	100	SY	4" CONCRETE SIDEWALK	4950000000-N	1267	5	EA	FLEXIBLE DELINEATORS (YELLOW & RED)	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING							
2598000000-E	848	50	SY	CONCRETE WHEELCHAIR RAMPS	4950000000-N	1267	5	EA	FLEXIBLE DELINEATORS (YELLOW & RED)	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING							
2600000000-N	SP	4	EA	RETROFIT EXISTING WHEELCHAIR RAMPS	5005000000-E	1401	4	EA	80' HIGH MOUNT STANDARD	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING							
2647000000-E	852	280	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	5020000000-N	1401	1	EA	PORTABLE DRIVE UNIT	6108000000-E	1665	1.25	TON	FERTILIZER TOPDRESSING							
2845000000-N	858	1	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5025000000-E	1402	12	CY	HIGH MOUNT FOUNDATIONS	6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING							
3656000000-E	876	300	SY	FILTER FABRIC FOR DRAINAGE	5070000000-N	1405	7	EA	STANDARD FOUNDATIONS ***** (R1)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL							
4072000000-E	903	667	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	5085000000-N	1406	24	EA	LIGHT STANDARD LUMINAIRES, TYPE RDW 250W HPS	7060000000-E	1705	4,800	LF	SIGNAL CABLE							
4102000000-N	904	13	EA	SIGN ERECTION, TYPE E	5125000000-E	1407	50	LF	ELECTRIC SERVICE LATERAL ***** (3#10, USE)	7072000000-E	1705	21	EA	VEHICLE SIGNAL HEAD (***, ** SECTION) (12", 3 SECTION, DARK GREEN)							
4108000000-N	904	12	EA	SIGN ERECTION, TYPE F	5145000000-N	1408	1	EA	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	7072000000-E	1705	1	EA	VEHICLE SIGNAL HEAD (***, ** SECTION) (12", 5 SECTION, DARK GREEN)							
4129000000-N	906	3	EA	RELOCATE SIGN, TYPE ***** (D)	5155000000-E	1409	300	LF	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	7252000000-E	1710	250	LF	MESSENGER CABLE (1/4")							
4155000000-N	907	28	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5160000000-E	1409	530	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	7279000000-E	1715	1,210	LF	TRACER WIRE							
4237000000-N	907	1	EA	STOCKPILE SIGN, D, E OR F	5160000000-E	1409	530	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	7300000000-E	1715	420	LF	TRENCHING (UNPAVED)							
4412000000-E	SP	361	SF	WORK ZONE SIGNS (STATIONARY)	5160000000-E	1409	75	LF	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	7301000000-E	SP	1,210	LF	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 1)							
4412100000-E	SP	118	SF	WORK ZONE SIGNS (PORTABLE)	5170000000-E	1410	1,540	LF	** #8 W/G FEEDER CIRCUIT (2)	7310000000-E	SP	850	LF	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)							
4412200000-E	SP	68	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	5170000000-E	1410	1,540	LF	** #8 W/G FEEDER CIRCUIT (2)	7324000000-N	1716	17	EA	JUNCTION BOX (STANDARD SIZE)							
4415000000-N	1115	2	EA	FLASHING ARROW PANELS, TYPE C	5175000000-E	1410	990	LF	** #6 W/G FEEDER CIRCUIT (2)	7336000000-N	1716	12	EA	JUNCTION BOX (OVER-SIZED)							
4420000000-N	1120	5	EA	CHANGEABLE MESSAGE SIGNS	5180000000-E	1410	510	LF	** #4 W/G FEEDER CIRCUIT (2)	7444000000-E	1725	4,800	LF	INDUCTIVE LOOP SAWCUT							
4425000000-N	1125	1	EA	WARNING FLAG SETS	5185000000-E	1410	320	LF	** #2 W/G FEEDER CIRCUIT (2)	7456000000-E	1726	3,790	LF	LEAD-IN CABLE							
4430000000-N	1130	110	EA	DRUMS	5205000000-E	1410	2,090	LF	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	7516000000-E	1730	1,860	LF	COMMUNICATIONS CABLE (**FIBER) (12)							
4435000000-N	1135	110	EA	CONES	5210000000-E	1410	260	LF	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	7520000000-N	1731	3	EA	INTERCONNECT CENTER							
4446100000-E	SP	144	LF	BARRICADES (TYPE III)	5215000000-E	1410	540	LF	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	7564000000-N	1732	3	EA	FIBER-OPTIC TRANSCEIVER							
4455000000-N	1150	30	MD	FLAGGER	5215000000-E	1410	540	LF	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	7566000000-N	1733	4	EA	DELINEATOR MARKER							
4475000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	5220000000-E	1410	690	LF	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	7613000000-N	SP	10	EA	SOIL TEST							
4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	5240000000-N	1411	9	EA	ELECTRICAL JUNCTION BOXES ***** (PC18)	7614000000-E	SP	150	LF	DRILLED PIER FOUNDATION (** DIA) (48")							
4507000000-E	SP	349	LF	WATER FILLED BARRIER						7631000000-N	1744	10	EA	MAST ARM WITH METAL POLE DESIGN							

5/28/99
10-JAN-2005 07:27
TFDuncan rd-02oce34