

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+30 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	144 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	188 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60 LF		
0013	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	32 LF		
0014	0995000000-E	340	PIPE REMOVAL	253.1 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	325 TON		
0017	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	245 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0023	2043000000-E	815	4" PERFORATED SUBDRAIN PIPE	500 LF		
0024	2054000000-E	815	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2076000000-E	815	4" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0028	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	50 LF		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	90 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	400 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3635000000-E	876	PLAIN RIP RAP, CLASS II	160 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	540 SY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	473 SF		
0039	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0040	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0041	4430000000-N	1130	DRUMS	30 EA		
0042	4446100000-E	SP	BARRICADES (TYPE III)	144 LF		
0043	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	3,620 LF		
0044	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	46 TON		
0045	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	46 TON		
0046	5360000000-E	1510	6" DI WATER PIPE, PC 350	856 LF		
0047	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	300 LB		
0048	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	2 EA		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	535 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	135 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	145 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6029000000-E	SP	SAFETY FENCE	300 LF		
0057	6030000000-E	1630	SILT EXCAVATION	400 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	520 SY		
0059	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,700 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0061	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0069	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0070	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+30.00-L-)	Lump Sum	L.S.	
0071	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+30.00-L-)	Lump Sum	L.S.	
0072	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	34 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	18 LF		
0074	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	35 LF		
0075	8113000000-N	SP	SID INSPECTION	2 EA		
0076	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0077	8116000000-E	SP	CSL TUBES	227.8 LF		
0078	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	788 CY		
0079	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	56.5 CY		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+30.00-L-)	Lump Sum	L.S.	
0081	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,343 LB		
0082	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,186 LB		
0083	8364000000-E	450	HP12X53 STEEL PILES	315 LF		
0084	8503000000-E	460	CONCRETE BARRIER RAIL	275.08 LF		
0085	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	245 TON		
0086	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	278 SY		
0087	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0088	8753000000-E	SP	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	1,650.5 LF		

C201292 (B-4047)
COUNTY: Burke County

2/16/99

Contract No: C201292
County: Burke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General