

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201274

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	2044000000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE	6000000000-E	1605	650	LF	TEMPORARY SILT FENCE
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (16+59.00 -L-)	2055000000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6006000000-E	1610	100	TON	STONE FOR EROSION CONTROL, CLASS A
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING	2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	6009000000-E	1610	375	TON	STONE FOR EROSION CONTROL, CLASS B
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	6012000000-E	1610	110	TON	SEDIMENT CONTROL STONE
0063000000-N	SP	Lump Sum		GRADING	2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	6015000000-E	1615	2.5	ACR	TEMPORARY MULCHING
0080000000-E	SP	200	TON	CLASS IV SUBGRADE STABILIZA- TION	2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
0106000000-E	230	10,600	CY	BORROW EXCAVATION	2556000000-E	846	485	LF	SHOULDER BERM GUTTER	6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
0134000000-E	240	149	CY	DRAINAGE DITCH EXCAVATION	3030000000-E	862	1,000	LF	STEEL BM GUARDRAIL	6024000000-E	1622	70	LF	TEMPORARY SLOPE DRAINS
0195000000-E	265	200	CY	SELECT GRANULAR MATERIAL	3045000000-E	862	75	LF	STEEL BM GUARDRAIL, SHOP CURVED	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0196000000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6029000000-E	SP	330	LF	SAFETY FENCE
0318000000-E	300	19	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3195000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	6030000000-E	1630	1,350	CY	SILT EXCAVATION
0343000000-E	310	60	LF	15" SIDE DRAIN PIPE	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6036000000-E	1631	750	SY	MATting FOR EROSION CONTROL
0366000000-E	310	60	LF	15" RC PIPE CULVERTS, CLASS III	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6038000000-E	SP	250	SY	PERMANENT SOIL REINFORCEMENT MAT
0708000000-E	310	56	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	3621000000-E	876	21	SY	PLAIN RIP RAP, CLASS II	6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3649000000-E	876	4	TON	PLAIN RIP RAP, CLASS B	6084000000-E	1660	3	ACR	SEEDING & MULCHING
0995000000-E	340	50	LF	PIPE REMOVAL	3656000000-E	876	314	SY	FILTER FABRIC FOR DRAINAGE	6087000000-E	1660	1.5	ACR	MOWING
1121000000-E	520	81	TON	AGGREGATE BASE COURSE	4412000000-E	SP	400	SF	WORK ZONE SIGNS (STATIONARY)	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
1220000000-E	545	200	TON	INCIDENTAL STONE BASE	4412100000-E	SP	144	SF	WORK ZONE SIGNS (PORTABLE)	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1489000000-E	610	1,010	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4412200000-E	SP	100	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
1525000000-E	SP	650	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4425000000-N	1125	4	EA	WARNING FLAG SETS	6108000000-E	1665	2.25	TON	FERTILIZER TOPDRESSING
1560000000-E	620	86	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4430000000-N	1130	50	EA	DRUMS	6114000000-N	SP	3	HR	SPECIALIZED HAND MOWING
1693000000-E	654	28	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4435000000-N	1135	30	EA	CONES	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
2022000000-E	815	45	CY	SUBDRAIN EXCAVATION	4446100000-E	SP	104	LF	BARRICADES (TYPE III)	6123000000-E	1670	0.25	ACR	REFORESTATION
2033000000-E	815	34	CY	SUBDRAIN FINE AGGREGATE	4450000000-N	1150	1,800	HR	FLAGGER					
					4810000000-E	1205	20,800	LF	PAINT PAVEMENT MARKING LINES (4")					

5/28/99

03-JUN-2005 11:53
R:\Roadway\Proj\B3857\rdy-sum.dgn
kmd\jgains AT RD223162