

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+59.00 -L-)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0007	0106000000-E	230	BORROW EXCAVATION	10,600 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	149 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	19 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	60 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	50 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	81 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,010 TON		
0020	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	650 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	86 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	28 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	485 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	1,000 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0038	3635000000-E	876	PLAIN RIP RAP, CLASS II	21 TON		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	4 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	314 SY		
0041	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	400 SF		
0042	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144 SF		
0043	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	100 SF		
0044	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0045	4430000000-N	1130	DRUMS	50 EA		
0046	4435000000-N	1135	CONES	30 EA		
0047	4446100000-E	SP	BARRICADES (TYPE III)	104 LF		
0048	4450000000-N	1150	FLAGGER	1,800 HR		
0049	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,800 LF		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	650 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	375 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0054	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0058	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0059	6029000000-E	SP	SAFETY FENCE	330 LF		
0060	6030000000-E	1630	SILT EXCAVATION	1,350 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	750 SY		
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250 SY		
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0065	6087000000-E	1660	MOWING	1.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0071	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0072	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+59.00 -L-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	37.2 CY		
0075	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+59.00 -L-)	Lump Sum	L.S.	
0076	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,350 LB		
0077	8364000000-E	450	HP12X53 STEEL PILES	480 LF		
0078	8468000000-E	460	ONE BAR METAL RAIL	160.5 LF		
0079	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" x 2'-0")	175.5 LF		
0080	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	494 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	549 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8753100000-E	SP	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,316.25 LF		
			Total Amount Of Bid For Entire Project :			

1147/Sep07/Q53337.7/D334489600000/E83

C201274 (B-3857)
COUNTY: Henderson County

2/16/99

Contract No: C201274
County: Henderson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General