

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201366

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	202200000-E	815	112	CY	SUBDRAIN EXCAVATION	481000000-E	1205	16,496	LF	PAINT PAVEMENT MARKING LINES (4")
002200000-E	225	15,300	CY	UNCLASSIFIED EXCAVATION	203300000-E	815	84	CY	SUBDRAIN FINE AGGREGATE	600000000-E	1605	605	LF	TEMPORARY SILT FENCE
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.00)	204300000-E	815	500	LF	4" PERFORATED SUBDRAIN PIPE	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	205400000-E	815	15	EA	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	600900000-E	1610	405	TON	STONE FOR EROSION CONTROL, CLASS B
005700000-E	226	2,500	CY	UNDERCUT EXCAVATION	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	601200000-E	1610	195	TON	SEDIMENT CONTROL STONE
006300000-N	SP	Lump Sum		GRADING	207600000-E	815	6	LF	4" OUTLET PIPE (SUBDRAINS)	601500000-E	1615	4	ACR	TEMPORARY MULCHING
008000000-E	SP	3,000	TON	CLASS IV SUBGRADE STABILIZATION	228600000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES	601800000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
013400000-E	240	1,475	CY	DRAINAGE DITCH EXCAVATION	236600000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.24	602100000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
014100000-E	240	625	LF	BERM DITCH CONSTRUCTION	236700000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29	602400000-E	1622	160	LF	TEMPORARY SLOPE DRAINS
019500000-E	265	2,500	CY	SELECT GRANULAR MATERIAL	255600000-E	846	500	LF	SHOULDER BERM GUTTER	602700000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
019600000-E	270	2,500	SY	FABRIC FOR SOIL STABILIZATION	261900000-E	850	11	SY	4" CONCRETE PAVED DITCH	602900000-E	SP	550	LF	SAFETY FENCE
031800000-E	300	28	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	303000000-E	862	750	LF	STEEL BM GUARDRAIL	603000000-E	1630	550	CY	SILT EXCAVATION
036600000-E	310	88	LF	15" RC PIPE CULVERTS, CLASS III	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	603600000-E	1631	335	SY	MATTING FOR EROSION CONTROL
037200000-E	310	68	LF	18" RC PIPE CULVERTS, CLASS III	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	603800000-E	SP	945	SY	PERMANENT SOIL REINFORCEMENT MAT
070800000-E	310	108	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	604200000-E	1632	100	LF	1/4" HARDWARE CLOTH
072000000-E	310	56	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	362800000-E	876	500	TON	PLAIN RIP RAP, CLASS I	607000000-N	SP	4	EA	SPECIAL STILLING BASINS
080600000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	363500000-E	876	60	TON	PLAIN RIP RAP, CLASS II	608400000-E	1660	4.5	ACR	SEEDING & MULCHING
080800000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	364900000-E	876	6	TON	PLAIN RIP RAP, CLASS B	608700000-E	1660	2.5	ACR	MOWING
122000000-E	545	40	TON	INCIDENTAL STONE BASE	365600000-E	876	773	SY	FILTER FABRIC FOR DRAINAGE	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
148900000-E	610	850	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	441200000-E	SP	84	SF	WORK ZONE SIGNS (STATIONARY)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
152500000-E	SP	743	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	441210000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	609600000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
156000000-E	620	86	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	441220000-E	SP	32	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	610800000-E	1665	3.25	TON	FERTILIZER TOPDRESSING
200000000-N	806	17	EA	RIGHT OF WAY MARKERS	443000000-N	1130	20	EA	DRUMS	611400000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
					443500000-N	1135	20	EA	CONES	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
					444610000-E	SP	48	LF	BARRICADES (TYPE III)	612300000-E	1670	0.62	ACR	REFORESTATION
					445000000-N	1150	320	HR	FLAGGER					

REVISIONS

8/17/99