

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	15,300 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	3,000 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,475 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	625 LF		
001C	0195000000-E	265	SELECT GRANULAR MATERIAL	2,500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,500 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	28 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	88 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	68 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	108 LF		
0016	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0019	1220000000-E	545	INCIDENTAL STONE BASE	40 TON		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	850 TON		
0021	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	743 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	86 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	17 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0026	2043000000-E	815	4" PERFORATED SUBDRAIN PIPE	500 LF		
0027	2054000000-E	815	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2076000000-E	815	4" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	500 LF		
0034	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3030000000-E	862	STEEL BM GUARDRAIL	750 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0039	3628000000-E	876	PLAIN RIP RAP, CLASS I	500 TON		
0040	3635000000-E	876	PLAIN RIP RAP, CLASS II	60 TON		
0041	3649000000-E	876	PLAIN RIP RAP, CLASS B	6 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	773 SY		
0043	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	84 SF		
0044	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0045	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0046	4430000000-N	1130	DRUMS	20 EA		
0047	4435000000-N	1135	CONES	20 EA		
0048	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0049	4450000000-N	1150	FLAGGER	320 HR		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,496 LF		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	605 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	405 TON		
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	195 TON		
0055	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0058	6024000000-E	1622	TEMPORARY SLOPE DRAINS	160 LF		
0059	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
006C	6029000000-E	SP	SAFETY FENCE	550 LF		
0061	6030000000-E	1630	SILT EXCAVATION	550 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	335 SY		
0063	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	945 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0065	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0066	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0067	6087000000-E	1660	MOWING	2.5 ACR		
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0073	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0074	6123000000-E	1670	REFORESTATION	0.62 ACR		

STRUCTURE ITEMS

0075	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+05.00 -L-)	Lump Sum	L.S.	
0076	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
0077	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	36 LF		
0078	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	20 LF		
0079	8113000000-N	SP	SID INSPECTION	1 EA		
008C	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0081	8116000000-E	SP	CSL TUBES	264 LF		
0082	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,449.5 SF		
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	6,120 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	105.4 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	22,110 LB		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,826 LB		
0088	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	702.33 LF		
0089	8364000000-E	450	HP12X53 STEEL PILES	450 LF		
009C	8503000000-E	460	CONCRETE BARRIER RAIL	355.83 LF		
0091	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	944 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,050 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0754/Sep30/Q96150.43/D411149680000/E94

Total Amount Of Bid For Entire Project :

C201366 (B-4044)
COUNTY: Burke County

2/16/99

Contract No: C201366
County: Burke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General