Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
R-4733	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
35+50.00	0	0
36+00.00	0	1127
36+50.00	0	3170
37+00.00	0	4812
37+50.00	0	6456
38+00.00	0	7270
38+50.00	0	6499
39+00.00	0	5310
39+50.00	0	5265
40+00.00	0	5136
40+50.00	0	2315

Station -L2-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
29+00.00	0	0
29+50.00	408	0
30+00.00	1023	0
30+50.00	1733	0
31+00.00	2513	0
31+50.00	3488	0
32+00.00	4590	0
32+50.00	5964	0
33+00.00	7349	0
33+50.00	7880	5
34+00.00	8663	43
34+50.00	11735	38
35+00.00	15733	1
35+50.00	18524	1
36+00.00	19652	0
36+50.00	18118	0
37+00.00	15430	0
37+50.00	13436	0
38+00.00	11225	0
38+50.00	7669	3
39+00.00	3794	7
39+50.00	1212	9
40+00.00	105	10

Station DDE LT -L2-	D.D. Exc (cu. yd.)	
23+10.00	0	0
24+00.00	58	0