

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+80.65) | Lump Sum | L.S. | |
| 0003 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0004 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 400 CY | | |
| 0005 | 0063000000-N | SP | GRADING | Lump Sum | L.S. | |
| 0006 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 100 TON | | |
| 0007 | 0106000000-E | 230 | BORROW EXCAVATION | 8,850 CY | | |
| 0008 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 350 CY | | |
| 0009 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 400 CY | | |
| 0010 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 200 SY | | |
| 0011 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 10 TON | | |
| 0012 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 88 LF | | |
| 0013 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 4 EA | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0015 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 440 TON | | |
| 0016 | 1525000000-E | SP | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 350 TON | | |
| 0017 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 42 TON | | |

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-----------|-----------|--------|
| 0018 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 4 EA | | |
| 0019 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 112 CY | | |
| 002C | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 84 CY | | |
| 0021 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 500 LF | | |
| 0022 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 15 EA | | |
| 0023 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0024 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0025 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0026 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0027 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 265 LF | | |
| 0028 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 625 LF | | |
| 0029 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 003C | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0031 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0032 | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 15 TON | | |
| 0033 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 715 SY | | |
| 0034 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 EA | | |
| 0035 | 4412000000-E | SP | WORK ZONE SIGNS (STATIONARY) | 349 SF | | |

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0036 | 4412200000-E | SP | WORK ZONE SIGNS (BARRICADE MOUNTED) | 69 SF | | |
| 0037 | 4425000000-N | 1125 | WARNING FLAG SETS | 2 EA | | |
| 0038 | 4446100000-E | SP | BARRICADES (TYPE III) | 96 LF | | |
| 0039 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 8,800 LF | | |
| 004C | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 30 EA | | |
| 0041 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,500 LF | | |
| 0042 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 150 TON | | |
| 0043 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 180 TON | | |
| 0044 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 240 TON | | |
| 0045 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3 ACR | | |
| 0046 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 0047 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 0.5 TON | | |
| 0048 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 70 LF | | |
| 0049 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 2 EA | | |
| 005C | 6029000000-E | SP | SAFETY FENCE | 200 LF | | |
| 0051 | 6030000000-E | 1630 | SILT EXCAVATION | 760 CY | | |
| 0052 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 210 SY | | |

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|----------------------------------|----------|-----------|--------|
| 0053 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 1,250 SY | | |
| 0054 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 40 LF | | |
| 0055 | 6048000000-E | SP | FLOATING TURBIDITY CURTAIN | 60 SY | | |
| 0056 | 6070000000-N | SP | SPECIAL STILLING BASINS | 8 EA | | |
| 0057 | 6084000000-E | 1660 | SEEDING & MULCHING | 3.5 ACR | | |
| 0058 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0059 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 006C | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0061 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 LB | | |
| 0062 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.5 TON | | |
| 0063 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2.5 HR | | |
| 0064 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0065 | 6123000000-E | 1670 | REFORESTATION | 0.25 ACR | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|--|----------|------|--|
| 0066 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (25+80.65 -L-) | Lump Sum | L.S. | |
| 0067 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25+80.65 -L-) | Lump Sum | L.S. | |
| 0068 | 8105540000-E | SP | 3'-6" DIA DRILLED PIERS IN SO IL | 77.8 LF | | |

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0069 | 8105640000-E | SP | 3'-6" DIA DRILLED PIERS NOT IN SOIL | 31 LF | | |
| 0070 | 8111400000-E | SP | PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER | 48.8 LF | | |
| 0071 | 8113000000-N | SP | SID INSPECTION | 2 EA | | |
| 0072 | 8115000000-N | SP | CROSSHOLE SONIC LOGGING | 2 EA | | |
| 0073 | 8116000000-E | SP | CSL TUBES | 475.2 LF | | |
| 0074 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVATION | 1,510 CY | | |
| 0075 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 5,560 SF | | |
| 0076 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 5,134 SF | | |
| 0077 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 74.5 CY | | |
| 0078 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (25+80.65 -L-) | Lump Sum | L.S. | |
| 0079 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 20,872 LB | | |
| 0080 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 2,947 LB | | |
| 0081 | 8259000000-E | 430 | 36" PRESTRESSED CONCRETE GIRDERS | 702 LF | | |
| 0082 | 8364000000-E | 450 | HP12X53 STEEL PILES | 260 LF | | |
| 0083 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 355.83 LF | | |
| 0084 | 8608000000-E | 876 | PLAIN RIP RAP CLASS II (2'-0" THICK) | 691 TON | | |
| 0085 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 768 SY | | |

County : Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---|--------------|-------|---|----------|-----------|--------|
| 0086 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0087 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |
| 1051/Oct05/Q67477.63/D414110980000/E87 | | | Total Amount Of Bid For Entire Project : | | | |

C201364 (B-3877)
COUNTY: Nash County

2/16/99

Contract No: C201364
County: Nash

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General