

**NOTES :**

ASSUMED LIVE LOAD = HS 20 OR ALTERNATE LOADING.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

THIS BRIDGE HAS BEEN DESIGNED BY THE STRENGTH DESIGN METHOD AS SPECIFIED IN AASHTO STANDARD SPECIFICATIONS.

ALL STRUCTURAL STEEL SHALL BE AASHTO M270 GRADE 50W AND PAINTED IN ACCORDANCE WITH SYSTEM 4 OF ARTICLE 442-7 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED ON THE PLANS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

THE EXISTING STRUCTURE CONSISTING OF ONE 51'-0" TIMBER DECK SPAN WITH A CLEAR ROADWAY WIDTH OF 25'-0" ON STEEL I-BEAMS ON REINFORCED CONCRETE ABUTMENT (END BENT 1) AND TIMBER PILE AND CAP WITH CONCRETE SILLS (END BENT 2) AND LOCATED APPROXIMATELY 60'-0" DOWNSTREAM FROM THE PROPOSED STRUCTURE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED BELOW THE LEGAL LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE FURTHER DETERIORATE, THIS LOAD LIMITATION MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT. SEE SPECIAL PROVISION FOR "REMOVAL OF EXISTING STRUCTURE @ STA. 10+63.50 -L-".

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THE INFORMATION OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE INFORMATION INDICATED ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.


INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE AT STATION 10+63.50 -L-".

FOR LIMITS OF TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE TRAFFIC CONTROL PLANS. FOR PAY ITEM FOR TEMPORARY SHORING FOR MAINTENANCE OF TRAFFIC, SEE ROADWAY PLANS.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THERE IS NO SEPARATE PAYMENT FOR THE REMOVAL OF THE MATERIAL IN THE AREA OF END BENT 1. THIS MATERIAL SHALL BE REMOVED AND PAID FOR WITH THE INSTALLATION OF THE TEMPORARY SHORING.

SEE SHEET 3 OF 3 FOR ADDITIONAL NOTES.

SEE SHEET 2 OF 3 FOR FOUNDATION NOTES.



DRAWN BY : E. G. ALLEN    DATE : 8/30/05  
CHECKED BY : I. L. CLELLAND    DATE : 9/29/05

14-NOV-2005 10:10  
Q:\Structures\gallen\b3805gd.dgn  
gallen

Norman W. Beckett, Jr.  
11-14-05

Seal of Norman W. Beckett, Jr., Professional Engineer, No. 14855, State of North Carolina.

PROJECT NO. B-3805  
ASHE COUNTY  
STATION: 10+63.50 -L-

SHEET 1 OF 3    REPLACES BRIDGE NO. 310

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
GENERAL DRAWING BRIDGE ON SR 1507 OVER BUFFALO CREEK BETWEEN NC 88 AND SR 1672					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					TOTAL SHEETS 26