

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,655 TON		
0004	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,371 TON		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,830 TON		
0006	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,394 TON		
0007	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0008	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	4 EA		
0009	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	62,032 LF		
0010	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	47,730 LF		
0011	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	250 LF		
0012	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	22 EA		
0013	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	465 EA		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	500 TON		

0850/Dec08/Q140255.0/D3713610000/E13

Total Amount Of Bid For Entire Project :