

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	10,300 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+81-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	34 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	100 LF		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,915 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	200 TON		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	65 TON		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	272 LF		
0017	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	68 LF		
0018	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	1 EA		
0020	0995000000-E	340	PIPE REMOVAL	104 LF		
0021	1121000000-E	520	AGGREGATE BASE COURSE	635 TON		
0022	1275000000-E	600	PRIME COAT	450 GAL		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	650 TON		
0024	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	645 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 TON		
0026	2022000000-E	815	SUBDRAIN EXCAVATION	225 CY		
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0029	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0030	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0031	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.5 LF		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0035	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	116 LF		
0037	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	545 LF		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3030000000-E	862	STEEL BM GUARDRAIL	287.5		LF
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5		LF
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0041	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (SHOP CURVED, TYPE III)	1		EA
0042	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1		EA
0043	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3		EA
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3		EA
0045	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	150		LF
0046	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	162.5		LF
0047	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (SHOP CURVED, TYPE III)	1		EA
0048	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE III)	3		EA
0049	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4		EA
0050	3635000000-E	876	PLAIN RIP RAP, CLASS II	10		TON
0051	3642000000-E	876	PLAIN RIP RAP, CLASS A	50		TON
0052	3649000000-E	876	PLAIN RIP RAP, CLASS B	62		TON
0053	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	620		SY
0054	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	71.9		SF

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	18 SF		
0056	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	76.82 SF		
0057	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	388 LF		
0058	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
0059	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0060	4108000000-N	904	SIGN ERECTION, TYPE F	10 EA		
0061	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		
0062	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	13 EA		
0063	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
0064	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0065	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	324 SF		
0066	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	138 SF		
0067	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0068	4425000000-N	1125	WARNING FLAG SETS	8 EA		
0069	4430000000-N	1130	DRUMS	50 EA		
0070	4435000000-N	1135	CONES	25 EA		
0071	4446100000-E	SP	BARRICADES (TYPE III)	140 LF		
0072	4450000000-N	1150	FLAGGER	480 HR		
0073	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	13 EA		
0075	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,444 LF		
0076	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,469 LF		
0077	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	20 LF		
0078	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,763 LF		
0079	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	170 LF		
0080	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	705 LF		
0081	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	45 LF		
0082	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	20 EA		
0083	6000000000-E	1605	TEMPORARY SILT FENCE	860 LF		
0084	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0085	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	395 TON		
0086	6012000000-E	1610	SEDIMENT CONTROL STONE	320 TON		
0087	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0088	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0089	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0090	6029000000-E	SP	SAFETY FENCE	400 LF		
0091	6030000000-E	1630	SILT EXCAVATION	1,320 CY		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,400	SY	
0093	6042000000-E	1632	1/4" HARDWARE CLOTH	140	LF	
0094	6070000000-N	SP	SPECIAL STILLING BASINS	6	EA	
0095	6084000000-E	1660	SEEDING & MULCHING	4	ACR	
0096	6087000000-E	1660	MOWING	2.5	ACR	
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	3	TON	
0101	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5	HR	
0102	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0103	6123000000-E	1670	REFORESTATION	0.33	ACR	

STRUCTURE ITEMS

0104	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (14+81.00 -L-)	Lump Sum	L.S.	
0105	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+81.00 -L-)	Lump Sum	L.S.	
0106	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	42	LF	
0107	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	42	LF	
0108	8113000000-N	SP	SID INSPECTION	2	EA	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0110	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+81.00 -L-)	Lump Sum	L.S.	
0111	8161000000-E	420	GROOVING BRIDGE FLOORS	2,923 SF		
0112	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	65.4 CY		
0113	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+81.00 -L-)	Lump Sum	L.S.	
0114	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,357 LB		
0115	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,591 LB		
0116	8468000000-E	460	ONE BAR METAL RAIL	162.65 LF		
0117	8517000000-E	460	1'-***"X ***** CONCRETE PARAPET (1'-0" X 1'-9 1/2")	178.8 LF		
0118	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	161 TON		
0119	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	179 SY		
0120	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0121	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0122	8753100000-E	SP	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	894.01 LF		
0123	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	2,488 SF		

1548/Nov14/Q73606.66/D514663840000/E123

Total Amount Of Bid For Entire Project :

C201270 (B-3205)
COUNTY: Madison County

2/16/99

Contract No: C201270
County: Madison

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General