

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201163

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0000950000-E	SP	2,200	SF	GENERIC MISCELLANEOUS ITEM ROCK PLATING
0022000000-E	225	96,000	CY	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+36.00 -L-)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	500	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-E	SP	1,000	TON	CLASS IV SUBGRADE STABILIZATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0199000000-E	SP	150	SF	TEMPORARY SHORING
0318000000-E	300	134	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	56	LF	15" SIDE DRAIN PIPE
0366000000-E	310	896	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	100	LF	18" RC PIPE CULVERTS, CLASS III
0588000000-E	310	108	LF	18" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	4	EA	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")
0708000000-E	310	92	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	30	LF	PIPE REMOVAL
1121000000-E	520	260	TON	AGGREGATE BASE COURSE
1220000000-E	545	75	TON	INCIDENTAL STONE BASE
1330000000-E	607	30	SY	INCIDENTAL MILLING
1489000000-E	610	1,290	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	640	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	780	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	133	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	55	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	12	EA	RIGHT OF WAY MARKERS
2022000000-E	815	155	CY	SUBDRAIN EXCAVATION
2033000000-E	815	80	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	450	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2220000000-E	838	2	CY	REINFORCED ENDWALLS
2264000000-E	840	0.35	CY	PIPE PLUGS
2286000000-N	840	12	EA	MASONRY DRAINAGE STRUCTURES
2308000000-E	840	20	LF	MASONRY DRAINAGE STRUCTURES
2366000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	8	EA	FRAME WITH TWO GRATES, STD 840.29
2396000000-N	840	2	EA	FRAME WITH COVER, STD 840.54
2462000000-E	SP	2	EA	*** SLUICE GATE (25")
2474000000-N	SP	Lump Sum		GENERIC DRAINAGE ITEM HAZARDOUS WASTE RETENTION BASIN
2556000000-E	846	960	LF	SHOULDER BERM GUTTER
3030000000-E	862	662.5	LF	STEEL BM GUARDRAIL
3045000000-E	862	75	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3360000000-E	863	760	LF	REMOVE EXISTING GUARDRAIL
3628000000-E	876	290	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	13	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,270	SY	FILTER FABRIC FOR DRAINAGE
4025000000-E	901	24	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)
4025000000-E	901	79	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	215	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4096000000-N	904	2	EA	SIGN ERECTION, TYPE D
4102000000-N	904	11	EA	SIGN ERECTION, TYPE E
4155000000-N	907	18	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4412000000-E	SP	296	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	170	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	47	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	2	EA	WARNING FLAG SETS
4430000000-N	1130	60	EA	DRUMS
4435000000-N	1135	60	EA	CONES
4446100000-E	SP	148	LF	BARRICADES (TYPE III)
4455000000-N	1150	120	MD	FLAGGER
4465000000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS
4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
4485000000-E	1170	40	LF	PORTABLE CONCRETE BARRIER
4615000000-E	1205	520	LF	REMOVABLE TAPE PAVEMENT MARKING LINES (4")
4650000000-N	1251	34	EA	TEMPORARY RAISED PAVEMENT MARKERS
4810000000-E	1205	8,904	LF	PAINT PAVEMENT MARKING LINES (4")
4835000000-E	1205	80	LF	PAINT PAVEMENT MARKING LINES (24")
4847000000-E	SP	5,704	LF	POLYUREA PAVEMENT MARKING LINES (4")
4847140000-E	SP	40	LF	POLYUREA PAVEMENT MARKING LINES (24")
4847220000-N	SP	5	EA	POLYUREA PAVEMENT MARKING SYMBOL
4850000000-E	1205	780	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
4905000000-N	1253	33	EA	SNOWPLOWABLE PAVEMENT MARKERS
6000000000-E	1605	950	LF	TEMPORARY SILT FENCE
6006000000-E	1610	225	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	550	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	490	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	8.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	300	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	1.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	115	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	600	LF	SAFETY FENCE
6030000000-E	1630	1,800	CY	SILT EXCAVATION
6036000000-E	1631	1,405	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	700	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	14	ACR	SEEDING & MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6087000000-E	1660	5	ACR	MOWING
6090000000-E	1661	100	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	200	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	10.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.2	ACR	REFORESTATION

07/21/2004 10:00:00 AM C:\proweb\proj\3300\rdh\esh\03.dgn