

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-DET- 12+50 TO 20+00	6986		1346		5640
SUBTOTAL	6986		1346		5640
-L- 11+00 TO 16+89.70 (BEGIN BRIDGE)	7		330	323	
SUBTOTAL	7		330	323	
-L- 17+37.30 (END BRIDGE) TO 20+50	37		52	15	
SUBTOTAL	37		52	15	
-L- W-DET- REMOVAL 11+00 TO 20+50	1842		577		1265
SUBTOTAL	1842		577		1265
PROJECT TOTAL	8865		2305	338	6905
WASTE TO REPLACE BORROW				-338	-338
LOSS TO CLEARING & GURBBING	-20				-20
TOTAL	8845		2305	0	6547
SAY	9000				

UNDERCUT EXCAVATION = 500 CY

SUMMARY OF PAVEMENT REMOVAL
 IN SQUARE YARDS

LOCATION	ASPHALT REMOVAL	ASPHALT BREAK UP	CONCRETE REMOVAL	CONCRETE BREAK UP
-DET- 11+00.88 TO 19+45.65	702			
-L- 14+50 TO 16+99+/-	540			
-L- 17+24+/- TO 19+50	417			
TOTAL	1659			
SAY	1675			

Note: Approximate quantities only. Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement and Removal of Existing Pavement will be paid for at the contract Lump Sum price for "Grading".

6/4/99
 11/24/2004 9:55:52 AM
 F:\Roadway\Pr-01\B3808_rdy_sum.dgn