

SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
002200000-E	225	9,000	CY	UNCLASSIFIED EXCAVATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+13.50)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
005700000-E	226	500	CY	UNDERCUT EXCAVATION
006300000-N	SP	Lump Sum		GRADING
008000000-E	SP	600	TON	CLASS IV SUBGRADE STABILIZATION
013400000-E	240	240	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
019900000-E	SP	65	SF	TEMPORARY SHORING
031800000-E	300	60	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034300000-E	310	28	LF	15" SIDE DRAIN PIPE
034500000-E	310	44	LF	24" SIDE DRAIN PIPE
037200000-E	310	36	LF	18" RC PIPE CULVERTS, CLASS III
038400000-E	310	56	LF	30" RC PIPE CULVERTS, CLASS III
057600000-E	310	212	LF	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")
058200000-E	310	52	LF	15" CS PIPE CULVERTS, 0.064" THICK
059400000-E	310	60	LF	24" CS PIPE CULVERTS, 0.064" THICK
072600000-E	310	68	LF	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK
099500000-E	340	526	LF	PIPE REMOVAL
112100000-E	520	335	TON	AGGREGATE BASE COURSE
122000000-E	545	75	TON	INCIDENTAL STONE BASE
148900000-E	610	410	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	575	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	55	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
186900000-E	710	2	SY	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (16")
200000000-N	806	16	EA	RIGHT OF WAY MARKERS
202200000-E	815	410	CY	SUBDRAIN EXCAVATION
203300000-E	815	210	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	1,200	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	36	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	3	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	18	LF	6" OUTLET PIPE (SUBDRAINS)
220900000-E	838	2	CY	ENDWALLS
222000000-E	838	10.6	CY	REINFORCED ENDWALLS
228600000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
248600000-E	SP	402.34	SF	GENERIC DRAINAGE ITEM TEMPORARY SANDBAG HEADWALL
255600000-E	846	45	LF	SHOULDER BERM GUTTER
272400000-E	857	200	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED
303000000-E	862	87.5	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
318000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (BIC)
321500000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
331700000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77
338000000-E	862	262.5	LF	TEMPORARY STEEL BM GUARDRAIL
338910000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
362800000-E	876	13	TON	PLAIN RIP RAP, CLASS I
364900000-E	876	200	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	830	SY	FILTER FABRIC FOR DRAINAGE
441200000-E	SP	160	SF	WORK ZONE SIGNS (STATIONARY)
441210000-E	SP	128	SF	WORK ZONE SIGNS (PORTABLE)
441220000-E	SP	36	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
443000000-N	1130	42	EA	DRUMS
443500000-N	1135	21	EA	CONES
444610000-E	SP	36	LF	BARRICADES (TYPE III)
445000000-N	1150	1,800	HR	FLAGGER
446000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)
447500000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
465000000-N	1251	62	EA	TEMPORARY RAISED PAVEMENT MARKERS
481000000-E	1205	21,200	LF	PAINT PAVEMENT MARKING LINES (4")
600000000-E	1605	550	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	195	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	290	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING

ItemNumber	Sec #	Quantity	Unit	Description
602400000-E	1622	65	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	990	LF	SAFETY FENCE
603000000-E	1630	1,015	CY	SILT EXCAVATION
603600000-E	1631	890	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	610	LF	1/4" HARDWARE CLOTH
607000000-N	SP	2	EA	SPECIAL STILLING BASINS
608400000-E	1660	2	ACR	SEEDING & MULCHING
608700000-E	1660	1	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
612300000-E	1670	0.7	ACR	REFORESTATION