

PROJECT NO.	SHEET NO.	TOTAL NO.
11CR.10061.8, 11CR.20061.8, 11CR.300618.8, ETC.	8	8

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	481000000-E	484700000-E		4847140000-E	4847200000-N	4847220000-N			4905000000-N
					4" TEMPORARY PAINT	POLYUREA LINES 4" YELLOW	POLYUREA LINES 4" WHITE	POLYUREA LINES 24"	POLYUREA CHARACTER	POLYUREA SYMBOL LT ARROW	POLYUREA SYMBOL STR ARROW	POLYUREA STR & LT ARROW	SNOW PLOWABLE MARKERS
					LF	LF	LF	EA	EA	EA	EA	EA	EA
11CR.10061.8	Avery	1	US 221	FROM NC 181 TO SR 1545		11,682.00	19,045.00						117
		2	US 19E	FROM SR 1166 TO SR 1130		31,020.00	50,572.00	100.00	12.00	1.00			310
TOTAL FOR PROJ NO. 11CR.10061.8						42,702.00	69,617.00	100	12	1			427
						112,319.00					1		
11CR.20061.8	Avery	3	SR 1337	FROM NC 184 TO END 18' PAVEMENT		11,220.00	18,292.00						112
		4	SR 1501	FROM SR 1504 TO SR 1544		17,820.00	29,052.00						178
TOTAL FOR PROJ NO. 11CR.20061.8						29,040.00	47,344.00						290
						76,384.00							
11CR.300618.8	Avery	5	SR 1342	NEWLAND: FROM NC 194 TO NCL NEWLAND		3,432.00	5,595.00						69
TOTAL FOR PROJ NO. 11CR.300618.8						3,432.00	5,595.00						69
						9,027.00							
11CR.10951.8	Watauga	6	NC 105	FROM AVERY COUNTY LINE TO END 3 LANE	9,900.00	6,600.00	14,060.00				2.00	2.00	132
		"	"	FROM END 3 LANE TO SR 1594	4,950.00	4,950.00	8,070.00						50
TOTAL FOR MAP NO. 6					14,850	11,550.00	22,130.00				2	2	182
TOTAL FOR PROJ NO. 11CR.10951.8					14,850	11,550.00	22,130.00				2	2	182
						33,680.00					4		
11CR.20951.8	Watauga	7	SR 1109	FROM NC 105 TO SR 1110		17,160.00	27,976.00						172
		8	SR 1159	FROM SR 1102 TO END OF PAVEMENT									
		9	SR 1557	FROM 1552 TO SR 1568		17,160.00	27,976.00						172
		10	SR 1603	FROM SR 1602 TO END OF MAINTENANCE									
TOTAL FOR PROJ NO. 11CR.20951.8						34,320	55,952						344
						90,272							
GRAND TOTAL					14,850	121,044	200,638	100	12	1	2	2	1,312
						321,682					5		