

STATE OF NORTH CAROLINA
SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
588800000-M	SP	60	M	GENERIC UTILITY ITEM 100MM PVC SEWER PIPE, SDR 35	602100000-M	1620	3.5	MTN	FERTILIZER FOR TEMPORARY SEED- ING	730100000-M	SP	460	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (50MM, 2)
588800000-M	SP	60	M	GENERIC UTILITY ITEM 150MM PVC SEWER PIPE, SDR 35	602400000-M	1622	290	M	TEMPORARY SLOPE DRAINS	730200000-M	SP	275	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 31.75MM (** CONDUIT) (1)
588800000-M	SP	300	M	GENERIC UTILITY ITEM 200MM DI SEWER PIPE, PC 2.41 MPA	602700000-N	1622	22	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	732400000-N	1716	99	EA	JUNCTION BOX (STANDARD SIZE)
588800000-M	SP	60	M	GENERIC UTILITY ITEM 200MM PVC SEWER PIPE, SDR 35	603000000-M	1630	7,600	M3	SILT EXCAVATION	733600000-N	1716	12	EA	JUNCTION BOX (OVER-SIZED)
588800000-M	SP	85	M	GENERIC UTILITY ITEM 250MM DI SEWER PIPE, PC 2.41MPA	603600000-M	1631	6,225	M2	MATTING FOR EROSION CONTROL	736000000-N	1720	16	EA	WOOD POLE
588800000-M	SP	410	M	GENERIC UTILITY ITEM 400MM DI SEWER PIPE, PC 1.72MPA	604200000-M	1632	1,260	M	6.4MM HARDWARE CLOTH	737200000-N	1721	66	EA	GUY ASSEMBLY
588800000-M	SP	740	M	GENERIC UTILITY ITEM 500MM DI SEWER PIPE, PC 1.72MPA	606900000-M	1638	600	M3	STILLING BASINS	738400000-M	1722	9	EA	*****MM RISER WITH ***** (50MM, FIBER OPTIC CABLE SEAL)
588800000-M	SP	28	M	GENERIC UTILITY ITEM PRECAST CONC MANHOLE WALL, 1200MM DIA, OVER 1.8M HT	608400000-M	1660	10.5	HA	SEEDING & MULCHING	740800000-M	1722	7	EA	25MM RISER WITH WEATHERHEAD
588800000-M	SP	2	M	GENERIC UTILITY ITEM PRECAST CONC MANHOLE WALL, 1500MM DIA, OVER 1.8M HT	608700000-M	1660	4.5	HA	MOWING	742000000-M	1722	15	EA	50MM RISER WITH WEATHERHEAD
588800000-M	SP	40	M	GENERIC UTILITY ITEM PRECAST CONC MANHOLE WALL, 1800MM DIA, OVER 1.8M HT	609000000-M	1661	100	KG	SEED FOR REPAIR SEEDING	744400000-M	1725	7,860	M	INDUCTIVE LOOP SAWCUT
588800000-M	SP	4	M	GENERIC UTILITY ITEM SEWER MANHOLE OUTSIDE DROP ASSEMBLY	609300000-M	1661	0.5	MTN	FERTILIZER FOR REPAIR SEEDING	745600000-M	1726	10,395	M	LEAD-IN CABLE
590600000-M	SP	3,761.8	KG	GENERIC UTILITY ITEM DI RESTRAINED JOINT WATER PIPE FITTINGS	609600000-M	1662	300	KG	SEED FOR SUPPLEMENTAL SEEDING	751600000-M	1730	4,550	M	COMMUNICATIONS CABLE (**FIBER) (12)
591800000-N	SP	2,160	HR	GENERIC UTILITY ITEM PROJECT COORDINATION BYPASS PUMPING	610800000-M	1665	17.5	MTN	FERTILIZER TOPDRESSING	752000000-N	1731	7	EA	INTERCONNECT CENTER
600000000-M	1605	2,150	M	TEMPORARY SILT FENCE	610900000-M	SP	0.05	HA	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLEUGRASS)	755200000-N	1733	11	EA	DELINEATOR MARKER
600600000-M	1610	555	MTN	STONE FOR EROSION CONTROL, CLASS A	611100000-M	SP	135	M	IMPERVIOUS DIKE	756600000-N	1733	11	EA	DELINEATOR MARKER
600900000-M	1610	2,680	MTN	STONE FOR EROSION CONTROL, CLASS B	611400000-N	SP	2	HR	SPECIALIZED HAND MOWING	756800000-N	SP	1	EA	FURNISH FIBER-OPTIC RESTORA- TION KIT
601200000-M	1610	2,180	MTN	SEDIMENT CONTROL STONE	611700000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL	757000000-N	SP	1	EA	FURNISH FIBER-OPTIC POWER ME- TER
601500000-M	1615	8	HA	TEMPORARY MULCHING	611700000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL	757200000-N	SP	1	EA	FURNISH OPTICAL LIGHT GENERA- TOR
601800000-M	1620	450	KG	SEED FOR TEMPORARY SEEDING	704800000-M	1705	20	EA	PEDESTRIAN SIGNAL HEAD (300MM, 2 SECTION)	757400000-N	SP	1	EA	FURNISH FIBER-OPTIC TRANSCIEV- ER
					706000000-M	1705	2,350	M	SIGNAL CABLE	758800000-N	1741	19	EA	SIGNAL SUPPORT MAST ARM WITH METAL POLE
					712000000-M	1705	45	EA	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	761300000-N	SP	19	EA	SOIL TEST
					713200000-M	1705	2	EA	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	761400000-M	SP	80	M	DRILLED PIER FOUNDATION (**MM DIA) (1066MM)
					714400000-M	1705	14	EA	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	761400000-M	SP	15	M	DRILLED PIER FOUNDATION (**MM DIA) (1219MM)
					725200000-M	1710	3,450	M	MESSENGER CABLE (6.35MM)	763600000-N	1745	3	EA	SIGN FOR SIGNALS
					726400000-M	1710	640	M	MESSENGER CABLE (9.52MM)	768400000-N	1750	7	EA	SIGNAL CABINET FOUNDATION
					727900000-M	1715	325	M	TRACER WIRE	768800000-N	SP	7	EA	CABINET BASE ADAPTER
					730000000-M	1715	2,685	M	TRENCHING (UNPAVED)	775600000-N	1751	7	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
										778000000-N	SP	61	EA	DETECTOR CARD (TYPE 2070L)
										793600000-N	SP	1	EA	CENTRAL COMPUTER
										793800000-N	SP	1	EA	NOTEBOOK COMPUTER
										794200000-N	SP	1	EA	PRINTER
										798000000-N	SP	7	EA	GENERIC SIGNAL ITEM (FIBER-OPTIC TRANSCIEVER-SELF HEALING RING)