

PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10231.3, 12CR.20231.3 12CR.302303.2, ETC.	4	6

# SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MANHOLES EA	METER OR VALVE BOX EA				
12CR.10231.3	Cleveland	1	NC 182	ECL FALLSTON TO LINCOLN CO. LINE	2	2.03	22	75	4.06	400	2,421	121	153	10						
			2	US 29 N	ECL GROVER TO NC 216 S	4	1.58	24	50	3.2	500	2,160	187	147	100					
			3	US 29 N	NC 216 S TO I-85 BRIDGE	4	1.67	24	50	3.3		2,332	198	157	100					
			4	US 29 S	ECL GROVER TO NC 216 S	4	1.58	24	50	3.2	500	2,215	187	150	100					
			5	US 29 S	NC 216 S TO I-85 BRIDGE	4	1.67	Var. 24-30	50	3.3		2,271	198	154	100					
<b>TOTAL FOR PROJ NO. 12CR.10231.3</b>						<b>8.53</b>		<b>275</b>	<b>17.06</b>	<b>1400</b>	<b>11,399</b>	<b>891</b>	<b>761</b>	<b>410</b>						
12CR.20231.3	Cleveland	6	SR 2252	SR 2250 TO SR 2256	1	1.02	20	25			1,106	50	74	75						
			7	SR 2467	NC 226 TO END MAINT	1	0.3	20	20			325	16	22	25					
			8	SR 2422	SR 1105 TO END MAINT	1	0.22	20	20			239	22	18	40					
			9	SR 1123	NC 150 TO SR 1151	1	2.41	22	60			3,170	132	203	75					
			10	SR 2070	SR 2069 TO SR 2071	1	0.36	18	10			352	25	27	75					
			11	SR 2071	SR 2070 TO SR 2636	1	0.8	18	25			781	34	58	150					
			12	SR 1320	SR 1315 TO SCL LATTIMORE	1	2.06	18	60			2,010	201	136	50					
			13	SR 1517	SR 1004 TO SR 1509	1	1.49	18	25			1,454	145	98	40					
			14	SR 1362	NC 226 TO SCL POLKVILLE	1	0.19	18	10			185	9	13	25					
			15	SR 1151	NC 150 TO SR 1147	1	1.74	18	100			1,698	170	114	50					
			16	SR 1147	SR 1151 TO SR 1146	1	1.27	18	40			1,239	62	80	25					
			17	SR 2245	SR 2283 TO SC LINE	1	2.52	18	100			2,459	246	167	75					
			18	SR 1912	NC 150 TO CL WACO	1	0.17	18	10			166	8	12	25					
			19	SR 2627	SR 2070 TO END MAINT	1	0.19	20	10			206	10	14	20					
			20	SR 2628	SR 2627 TO END MAINT	1	0.67	20	20			726	36	49	50					
			21	SR 2634	SR 2628 TO END MAINT	1	0.11	18	10			107	5	8	15					
			22	SR 2245	I-85 BRIDGE TO SR 2283	1	0.76	20	40		200	824	74	55	25					
			23	SR 1528	SR 1524 TO DEAD END	1	0.49	18	30			478		29				2		
			<b>TOTAL FOR PROJ NO. 12CR.20231.3</b>						<b>16.77</b>		<b>615</b>	<b>0</b>	<b>200</b>	<b>17,525</b>	<b>1,245</b>	<b>1,177</b>	<b>840</b>		<b>2</b>	
			12CR.302303.2	Cleveland	24	NC 150	ECL BOILING SPRINGS TO SR 1161	2	0.83					1,428	65	91	25	19	3	
						25	NC 150	SR 1161 TO W BRANCH ST	3	0.17	24	40	1.5		628	20	43	75	3	6
			<b>TOTAL FOR PROJ NO. 12CR.302303.2</b>						<b>1.24</b>		<b>90</b>	<b>1.5</b>	<b>0</b>	<b>2,056</b>	<b>85</b>	<b>134</b>	<b>100</b>	<b>22</b>	<b>9</b>	
12CR.302318.2	Cleveland	26	SR 2255	US 74 BUS TO END MAINT	1	0.16	18	10			142	14	10	10						
			27	SR 2254	US 74 BUS TO US 74 BUS	1	0.35	20	10			380	17	25	25					
			28	SR 2028	US 74 BUS TO US 74 BUS	1	0.51	18	25			452	45	32	40					
			29	SR 2029	SR 2028 TO SR 2028	1	0.17	18	10			151	15	11	20					
			30	SR 2030	US 74 BUS TO SR 2029	1	0.12	18	10			106	11	8	10					
			31	SR 2077	SR 2028 TO END MAINT	1	0.15	16	10			133	13	10	20					
<b>TOTAL FOR PROJ NO. 12CR.302318.2</b>						<b>1.46</b>		<b>75</b>	<b>0</b>	<b>0</b>	<b>1,364</b>	<b>115</b>	<b>96</b>	<b>125</b>						
12CR.302319.2	Cleveland	32	SR 1319	SCL LATTIMORE TO SAILOR ST	1	0.32	18	10			284	28	20	20						
<b>TOTAL FOR PROJ NO. 12CR.302319.2</b>						<b>0.32</b>		<b>10</b>	<b>0</b>	<b>0</b>	<b>284</b>	<b>28</b>	<b>20</b>	<b>20</b>						
12CR.302339.1	Cleveland	33	SR 1362	SCL POLKVILLE TO SR 1635	1	0.49	18	20			478	24	33	40						
			34	SR 1404	NC 226 TO NC 226	1	0.51	18	20			498	25	33	25					
<b>TOTAL FOR PROJ NO. 12CR.302339.1</b>						<b>1</b>		<b>40</b>	<b>0</b>	<b>0</b>	<b>976</b>	<b>49</b>	<b>66</b>	<b>65</b>						
12CR.302334.1	Cleveland	35	SR 1912	ECL WACO TO SR 1001	1	0.53	18	30			517	26	35	40						
<b>TOTAL FOR PROJ NO. 12CR.302334.1</b>						<b>0.53</b>		<b>30</b>	<b>0</b>	<b>0</b>	<b>517</b>	<b>26</b>	<b>35</b>	<b>40</b>						
12CR.302399.1	Cleveland	36	NC 182	SR 1001 TO ECL FALLSTON	2	0.25	22	90	0.5		298	15	19	10						
<b>TOTAL FOR PROJ NO. 12CR.302399.1</b>						<b>0.25</b>		<b>90</b>	<b>0.5</b>	<b>0</b>	<b>298</b>	<b>15</b>	<b>19</b>	<b>10</b>						
12CR.302314.1	Cleveland	37	US 29	SC LINE TO BEGIN 4-LANES	2	0.61	24	30	1.22		794	30	50	10						
<b>TOTAL FOR PROJ NO. 12CR.302314.1</b>						<b>0.61</b>		<b>30</b>	<b>1.22</b>	<b>0</b>	<b>794</b>	<b>30</b>	<b>50</b>	<b>10</b>						
<b>GRAND TOTAL</b>						<b>30.71</b>		<b>1255</b>	<b>20.28</b>	<b>1600</b>	<b>35,213</b>	<b>2,484</b>	<b>2,358</b>	<b>1,620</b>	<b>22</b>	<b>11</b>				