

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201122

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000800000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (20+93.00-L-)
003600000-E	225	600	CY	UNDERCUT EXCAVATION
004300000-N	226	Lump Sum		GRADING
008000000-E	SP	100	TON	CLASS IV SUBGRADE STABILIZATION
013400000-E	240	850	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	1,000	CY	SELECT GRANULAR MATERIAL
019600000-E	270	1,000	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	31	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034300000-E	310	16	LF	15" SIDE DRAIN PIPE
045300000-E	310	1	EA	*** PIPE END SECTION (15")
058200000-E	310	172	LF	15" CS PIPE CULVERTS, 0.064" THICK
070800000-E	310	48	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
099500000-E	340	194	LF	PIPE REMOVAL
112100000-E	520	3,000	TON	AGGREGATE BASE COURSE
122000000-E	545	30	TON	INCIDENTAL STONE BASE
133000000-E	607	125	SY	INCIDENTAL MILLING
148900000-E	610	675	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
149800000-E	610	850	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
151900000-E	610	1,150	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
156000000-E	620	140	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
200000000-N	806	11	EA	RIGHT OF WAY MARKERS
215400000-N	820	2	EA	METAL FUNNELS

ItemNumber	Sec #	Quantity	Unit	Description
216500000-E	820	52	LF	12" FUNNEL DRAIN PIPE
217600000-E	820	2	EA	12" FUNNEL DRAIN PIPE ELBOWS
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	140	LF	SHOULDER BERM GUTTER
303000000-E	862	375	LF	STEEL BM GUARDRAIL
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
338000000-E	862	775	LF	TEMPORARY STEEL BM GUARDRAIL
338700000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)
338910000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
362800000-E	876	40	TON	PLAIN RIP RAP, CLASS I
364900000-E	876	210	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	780	SY	FILTER FABRIC FOR DRAINAGE
402500000-E	901	14	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)
402500000-E	901	15	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
407200000-E	903	45	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
409600000-N	904	1	EA	SIGN ERECTION, TYPE D
410200000-N	904	1	EA	SIGN ERECTION, TYPE E
415500000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
440000000-E	1110	154	SF	WORK ZONE SIGNS (STATIONARY)
440500000-E	1110	128	SF	WORK ZONE SIGNS (PORTABLE)
441000000-E	1110	46	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
443000000-N	1130	72	EA	DRUMS

ItemNumber	Sec #	Quantity	Unit	Description
443500000-N	1135	30	EA	CONES
444500000-E	1145	72	LF	BARRICADES (TYPE III)
445000000-N	1150	900	HR	FLAGGER
446000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)
447500000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
465000000-N	1251	113	EA	TEMPORARY RAISED PAVEMENT MARKERS
468500000-E	1205	3,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
468600000-E	1205	3,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
481000000-E	1205	33,000	LF	PAINT PAVEMENT MARKING LINES (4")
485000000-E	1205	1,000	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
490500000-N	1253	20	EA	SNOWPLOWABLE PAVEMENT MARKERS
582200000-N	1530	1	EA	BREAK DOWN & REBUILD EXISTING MANHOLE
600000000-E	1605	565	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	450	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	215	TON	SEDIMENT CONTROL STONE
601500000-E	1615	3.5	ACR	TEMPORARY MULCHING
601800000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	160	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	6	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	250	LF	SAFETY FENCE
603000000-E	1630	4,210	CY	SILT EXCAVATION
603600000-E	1631	1,115	SY	MATTING FOR EROSION CONTROL
607000000-N	SP	4	EA	SPECIAL STILLING BASINS
608400000-E	1660	4.5	ACR	SEEDING & MULCHING
608700000-E	1660	2	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	3.25	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
612300000-E	1670	1	ACR	REFORESTATION