

STATE OF NORTH CAROLINA SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description
4725000000-M	1205	87	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)
4810000000-M	1205	44,970	M	PAINT PAVEMENT MARKING LINES (100MM)
4820000000-M	1205	1,350	M	PAINT PAVEMENT MARKING LINES (200MM)
4835000000-M	1205	300	M	PAINT PAVEMENT MARKING LINES (600MM)
4840000000-N	1205	8	EA	PAINT PAVEMENT MARKING CHARACTER
4845000000-N	1205	212	EA	PAINT PAVEMENT MARKING SYMBOL
4850000000-M	1205	22,300	M	REMOVAL OF PAVEMENT MARKING LINES (100MM)
4860000000-M	1205	1,350	M	REMOVAL OF PAVEMENT MARKING LINES (200MM)
4870000000-M	1205	110	M	REMOVAL OF PAVEMENT MARKING LINES (600MM)
4875000000-N	1205	20	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
4900000000-N	1252	140	EA	PERMANENT RAISED PAVEMENT MARKERS
4905000000-N	1253	840	EA	SNOWFLOWABLE PAVEMENT MARKERS
5300000000-M	1505	330	MTN	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
5312000000-M	1505	300	MTN	SELECT BACKFILL MATERIAL, UTILITIES CLASS **** (II)
5318000000-M	1505	30	MTN	PAVEMENT REPAIR FOR UTILITY WORK
5360000000-M	1510	86	M	150MM DI WATER PIPE, PC 2.41MPA
5366000000-M	1510	30	M	200MM DI WATER PIPE, PC 2.41MPA
5378000000-M	1510	6	M	300MM DI WATER PIPE, PC 2.41MPA
5408000000-M	1510	6	M	***MM COPPER WATER PIPE, TYPE K (50MM)
5414000000-M	1510	64	M	20MM COPPER WATER PIPE, TYPE K
5480000000-M	1510	1,294	KG	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP

ItemNumber	Sec #	Quantity	Unit	Description
5510000000-M	1510	1	EA	20MM CORPORATION STOP
5528000000-M	1510	1	EA	50MM CORPORATION STOP
5540000000-M	1510	1	EA	150MM GATE VALVE & VALVE BOX, 1.38MPA WP
5576000000-M	1510	1	EA	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ***MPA WP (150MM X 150MM, 1.38WP)
5582000000-M	1510	1	EA	*** X ***MM TAPPING SADDLE (200MM X 20MM)
5648000000-N	1510	11	EA	RELOCATE EXISTING WATER METER
5672000000-N	1510	10	EA	RELOCATE EXISTING FIRE HYDRANT
5690000000-M	1520	283	M	***MM PVC SEWER PIPE, SDR ** (100MM, 35)
5726000000-M	1520	443	M	200MM DI SEWER PIPE, PC 2.41MPA
5768000000-N	1520	21	EA	SANITARY SEWER CLEAN-OUT
5774000000-M	1525	6	EA	***MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH (1200MM)
5780000000-M	1525	7.6	M	PRECAST CONC MANHOLE WALL, ***MM DIA, OVER 1.8M HT (1200MM)
5882000000-N	SP	5	EA	GENERIC UTILITY ITEM BREAKDOWN & FILL ABANDONED SEPTIC TANK
5888000000-M	SP	80	M	GENERIC UTILITY ITEM 100MM PVC SEWER PIPE, SCH 40
5900000000-M	SP	600	MTN	GENERIC UTILITY ITEM #67 BEDDING STONE
6000000000-M	1605	2,300	M	TEMPORARY SILT FENCE
6006000000-M	1610	405	MTN	STONE FOR EROSION CONTROL, CLASS A
6009000000-M	1610	2,015	MTN	STONE FOR EROSION CONTROL, CLASS B
6012000000-M	1610	1,725	MTN	SEDIMENT CONTROL STONE
6015000000-M	1615	7.5	HA	TEMPORARY MULCHING
6018000000-M	1620	300	KG	SEED FOR TEMPORARY SEEDING
6021000000-M	1620	2.5	MTN	FERTILIZER FOR TEMPORARY SEEDING

ItemNumber	Sec #	Quantity	Unit	Description
6029000000-M	SP	300	M	SAFETY FENCE
6030000000-M	1630	3,425	M3	SILT EXCAVATION
6036000000-M	1631	4,620	M2	MATting FOR EROSION CONTROL
6038000000-M	SP	2,575	M2	PERMANENT SOIL REINFORCEMENT MAT
6042000000-M	1632	1,150	M	6.4MM HARDWARE CLOTH
6084000000-M	1660	7	HA	SEEDING & MULCHING
6087000000-M	1660	4.5	HA	MOWING
6090000000-M	1661	100	KG	SEED FOR REPAIR SEEDING
6093000000-M	1661	0.5	MTN	FERTILIZER FOR REPAIR SEEDING
6096000000-M	1662	200	KG	SEED FOR SUPPLEMENTAL SEEDING
6108000000-M	1665	11.75	MTN	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	12	EA	RESPONSE FOR EROSION CONTROL
7060000000-M	1705	770	M	SIGNAL CABLE
7120000000-M	1705	19	EA	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)
7144000000-M	1705	6	EA	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)
7252000000-M	1710	470	M	MESSENGER CABLE (6.35MM)
7300000000-M	1715	260	M	TRENCHING (UNPAVED)
7301000000-M	SP	25	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ****MM (** CONDUIT) (50MM, 1)
7324000000-N	1716	9	EA	JUNCTION BOX (STANDARD SIZE)
7336000000-N	1716	1	EA	JUNCTION BOX (OVER-SIZED)
7360000000-N	1720	4	EA	WOOD POLE
7372000000-N	1721	9	EA	GUY ASSEMBLY
7408000000-M	1722	1	EA	25MM RISER WITH WEATHERHEAD
7420000000-M	1722	4	EA	50MM RISER WITH WEATHERHEAD
7432000000-M	1722	1	EA	50MM RISER WITH HEAT SHRINK TUBING

ItemNumber	Sec #	Quantity	Unit	Description
7444000000-M	1725	960	M	INDUCTIVE LOOP SAWCUT
7456000000-M	1726	780	M	LEAD-IN CABLE
7481000000-N	SP	1	EA	SITE SURVEY
7481200000-N	SP	4	EA	LUMINAIRE ARM FOR VIDEO SYSTEM
7481280000-N	SP	4	EA	RELOCATE CAMERA SENSOR UNIT
7516000000-M	1730	180	M	COMMUNICATIONS CABLE (**FIBER) (12)
7540000000-N	1731	1	EA	AERIAL SPLICE ENCLOSURE
7552000000-N	1731	1	EA	INTERCONNECT CENTER
7568000000-N	SP	1	EA	FURNISH FIBER-OPTIC RESTORATION KIT
7575180000-N	SP	7	EA	CABLE TRANSFER
7576000000-N	1740	4	EA	METAL STRAIN SIGNAL POLE
7613000000-N	SP	4	EA	SOIL TEST
7614000000-M	SP	20	M	DRILLED PIER FOUNDATION (**MM DIA) (1067MM)
7684000000-N	1750	1	EA	SIGNAL CABINET FOUNDATION
7828000000-N	1751	1	EA	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)
7852000000-N	SP	16	EA	DETECTOR CARD (NEMA TS-2)

***** BEGIN SCHEDULE HA *****				
***** (2 ALTERNATES) *****				
7481220000-N HA1	SP	4	EA	CAMERA WITH INTERNAL LOOP EMULATOR PROCESSING UNIT
*** OR ***				
7481240000-N HA2	SP	4	EA	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT
7481260000-N HA2	SP	1	EA	EXTERNAL LOOP EMULATOR PROCESSING UNIT
***** END SCHEDULE HA *****				