

STATE OF NORTH CAROLINA
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201418

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0015000000-N	205	3	EA	SEALING ABANDONED WELLS
0050000000-M	226	0.4	HA	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-M	226	11,000	M3	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-M	SP	23,000	MTN	CLASS IV SUBGRADE STABILIZATION
0106000000-M	230	7,600	M3	BORROW EXCAVATION
0134000000-M	240	383	M3	DRAINAGE DITCH EXCAVATION
0195000000-M	265	1,000	M3	SELECT GRANULAR MATERIAL
0196000000-M	270	22,000	M2	FABRIC FOR SOIL STABILIZATION
0199000000-M	SP	200	M2	TEMPORARY SHORING
0318000000-M	300	1,210	MTN	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0360000000-M	310	33.6	M	300MM RC PIPE CULVERTS, CLASS III
0366000000-M	310	2,469.6	M	375MM RC PIPE CULVERTS, CLASS III
0372000000-M	310	624	M	450MM RC PIPE CULVERTS, CLASS III
0378000000-M	310	501.6	M	600MM RC PIPE CULVERTS, CLASS III
0384000000-M	310	24	M	750MM RC PIPE CULVERTS, CLASS III
0390000000-M	310	30	M	900MM RC PIPE CULVERTS, CLASS III
0708000000-M	310	6	M	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK
0806000000-M	310	2	EA	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK
0986000000-M	SP	58.8	M	GENERIC PIPE ITEM 450MM PLASTIC PIPE
0986000000-M	SP	60	M	GENERIC PIPE ITEM 750MM PLASTIC PIPE
0995000000-M	340	775	M	PIPE REMOVAL
0996000000-N	350	5	EA	PIPE CLEAN-OUT
ItemNumber	Sec #	Quantity	Unit	Description
1110000000-M	510	650	MTN	STABILIZER AGGREGATE
1121000000-M	520	350	MTN	AGGREGATE BASE COURSE
1220000000-M	545	500	MTN	INCIDENTAL STONE BASE
1297000000-M	607	13,420	M2	MILLING ASPHALT PAVEMENT, **MM DEPTH (65MM)
1330000000-M	607	1,450	M2	INCIDENTAL MILLING
1491000000-M	610	19,300	MTN	ASPHALT CONC BASE COURSE, TYPE B25.0C
1503000000-M	610	16,800	MTN	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
1523000000-M	610	13,100	MTN	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1560000000-M	620	1,620	MTN	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1565000000-M	620	852	MTN	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
1693000000-M	654	300	MTN	ASPHALT PLANT MIX PAVEMENT REPAIR
2022000000-M	815	276	M3	SUBDRAIN EXCAVATION
2033000000-M	815	207	M3	SUBDRAIN FINE AGGREGATE
2044000000-M	815	500	M	150MM PERFORATED SUBDRAIN PIPE
2055000000-M	815	51	EA	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	4	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-M	815	8	M	150MM OUTLET PIPE (SUBDRAINS)
2190000000-N	828	17	EA	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE
2253000000-M	840	1	M3	PIPE COLLARS
2264000000-M	840	1.5	M3	PIPE PLUGS
2275000000-M	SP	35	M3	FLOWABLE FILL
2286000000-N	840	179	EA	MASONRY DRAINAGE STRUCTURES
2308000000-M	840	8	M	MASONRY DRAINAGE STRUCTURES
2364000000-N	840	40	EA	FRAME WITH TWO GRATES, STD 840.16

ItemNumber	Sec #	Quantity	Unit	Description
2366000000-N	840	14	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	17	EA	FRAME WITH TWO GRATES, STD 840.29
2374000000-N	840	20	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)
2374000000-N	840	43	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
2374000000-N	840	42	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
2396000000-N	840	2	EA	FRAME WITH COVER, STD 840.54
2451000000-N	840	30	EA	CONCRETE APRON FOR DROP INLETS
2484000000-M	SP	18	M	GENERIC DRAINAGE ITEM 100MM POLYMER DRAIN LINE
2535000000-M	846	100	M	*** X ***MM CONCRETE CURB (200MM X 300MM)
2542000000-M	846	1,200	M	450MM CONCRETE CURB & GUTTER
2549000000-M	846	5,150	M	750MM CONCRETE CURB & GUTTER
2570000000-N	SP	2	EA	MODIFIED CONCRETE FLUME
2577000000-M	846	60	M	CONCRETE EXPRESSWAY GUTTER
2591000000-M	848	625	M2	100MM CONCRETE SIDEWALK
2598000000-M	848	50	M2	CONCRETE WHEELCHAIR RAMPS
2612000000-M	848	1,100	M2	150MM CONCRETE DRIVEWAY
2619000000-M	850	5	M2	100MM CONCRETE PAVED DITCH
2655000000-M	852	2,100	M2	125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN)
2830000000-N	858	5	EA	ADJUSTMENT OF MANHOLES
2845000000-N	858	55	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
2950000000-N	SP	1	EA	CONVERT EXISTING JUNCTION BOX TO DROP INLET
3030000000-M	862	53.34	M	STEEL BM GUARDRAIL
3105000000-N	862	4	EA	STEEL BM GUARDRAIL TERMINAL SECTIONS
ItemNumber	Sec #	Quantity	Unit	Description
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3536000000-M	866	11	M	CHAIN LINK FENCE, 1200MM FABRIC
3539000000-E	866	3	EA	METAL LINE POSTS FOR *** CHAIN LINK FENCE (1200MM)
3545000000-E	866	3	EA	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (1200MM)
3575000000-M	SP	275	M	GENERIC FENCING ITEM REMOVE, STOCKPILE, & RESET FENCE
3579000000-N	866	85	EA	GENERIC FENCING ITEM TEMP METAL LINE POSTS - 1800MM FENCE
3579000000-N	866	11	EA	GENERIC FENCING ITEM TEMP METAL TERM POSTS - 1800MM FENCE
3580000000-M	866	307	M	GENERIC FENCING ITEM TEMPORARY 1800MM CHAIN LINK FENCE
3649000000-M	876	55	MTN	PLAIN RIP RAP, CLASS B
3656000000-M	876	769	M2	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	8	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
3980000000-M	SP	135	M3	GENERIC WALL ITEM CONCRETE RETAINING WALL WITH BRICK VENEER
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM CONCRETE CANTILEVER RETAINING WALL
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM MODULAR BLOCK RETAINING WALL STA 10+46 TO 10+74 -Y14-
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM MODULAR BLOCK RETAINING WALL STA 13+52 TO 13+87 -Y14-
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM MODULAR BLOCK RETAINING WALL STA 14+06 TO 14+20 -Y14-
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM MODULAR BLOCK RETAINING WALL STA 57+34.739 TO 57+75.000 -L-
4072000000-M	903	620	M	SUPPORTS, 4.5KG STEEL U-CHANNEL

ItemNumber	Sec #	Quantity	Unit	Description
4096000000-N	904	3	EA	SIGN ERECTION, TYPE D
4102000000-N	904	138	EA	SIGN ERECTION, TYPE E
4129000000-N	906	2	EA	RELOCATE SIGN, TYPE ***** (D)
4155000000-N	907	32	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4158000000-N	907	2	EA	DISPOSAL OF SIGN SYSTEM, WOOD
4192000000-N	907	2	EA	DISPOSAL OF SUPPORT, U-CHANNEL
4412000000-M	SP	61	M2	WORK ZONE SIGNS (STATIONARY)
4412100000-M	SP	64	M2	WORK ZONE SIGNS (PORTABLE)
4412200000-M	SP	6	M2	WORK ZONE SIGNS (BARRICADE MOUNTED)
4415000000-N	1115	2	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS
4430000000-N	1130	200	EA	DRUMS
4435000000-N	1135	100	EA	CONES
4446100000-M	SP	180	M	BARRICADES (TYPE III)
4455000000-N	1150	600	MD	FLAGGER
4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
4470000000-N	1160	8	EA	RESET TEMPORARY CRASH CUSHIONS
4475000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
4507000000-M	SP	60	M	WATER FILLED BARRIER
4510000000-N	SP	480	HR	POLICE
4650000000-N	1251	3,110	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-M	1205	900	M	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)
4686000000-M	1205	5,370	M	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)
4695000000-M	1205	375	M	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)
4710000000-M	1205	80	M	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)