



# SURVEY CONTROL SHEET B-3350

PROJECT REFERENCE NO. B-3350	SHEET NO. 1-C
Location and Surveys	

BL	POINT	DESC.	NORTH	EAST	ELEVATION	L STATION	OFFSET
1	B3350-1		837793.2790	1455032.3270	991.31	OUTSIDE PROJECT LIMITS	
2	B3350-2		838706.6930	1455543.6180	918.02	13+42.64	47.54 RT
20	(EQUALITY NOT SET)		839011.8090	1455327.2954	UNKNOWN	17+03.40	10.38 LT
3	BL-3		839186.6580	1455203.3300	881.76	19+13.63	16.08 LT
4	BL-4		839594.7430	1455337.7420	907.19	23+42.52	24.76 LT

\*\*\*\*\*  
 BM 101      867.74  
 N 838991    E 1455059  
 L STATION 18+41 234 LEFT  
 R/R SPIKE SET IN BASE OF 48" TRIPLE  
 FORKED SYCAMORE 60' NORTH OF THE  
 NORTH BANK OF HUNTING CREEK  
 \*\*\*\*\*

\*\*\*\*\*  
 BM 102      923.81  
 N 839755    E 1455581  
 L STATION 23+61.33  
 N 51° 44' 04" E DIST    270.56  
 R/R SPIKE SET IN BASE OF 18" OAK  
 40' NORTH OF NORTH EP  
 \*\*\*\*\*



**DATUM DESCRIPTION**

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "B3350-1"

WITH NAD 1983/95 STATE PLANE GRID COORDINATES OF  
 NORTHING: 837793.2790(E) EASTING: 1455032.3270(E)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT  
 (GROUND TO GRID) IS: 0.999924400

THE N.C. LAMBERT GRID BEARING AND  
 LOCALIZED HORIZONTAL GROUND DISTANCE FROM  
 "B3350-1" TO -L- STATION 10+00.00 IS  
 N 31°19'33.86" E    692.06

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES  
 VERTICAL DATUM USED IS NAVD 88

**NOTES:**

THE CONTROL DATA FOR THIS PROJECT CAN BE FOUND ELECTRONICALLY BY SELECTING PROJECT CONTROL DATA AT:  
[HTTP://WWW.DOH.DOT.STATE.NC.US/PRECONSTRUCT/HIGHWAY/LOCATION/PROJECT](http://www.doh.dot.state.nc.us/preconstruct/highway/location/project)

SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT.  
 IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

⊙ INDICATES GEODETIC CONTROL MONUMENTS USED OR SET FOR HORIZONTAL PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT.

PROJECT CONTROL ESTABLISHED USING GLOBAL POSITIONING SYSTEM.

**NOTE: DRAWING NOT TO SCALE**

27-OCT-2004 13:47  
 D:\MCP\B3350\1s-1c\_041025.dgn  
 DWG:Gardner