5/28/99

PROJECT REFERENCE NO.	SHEET NO.
U-4008	3 (10F2)

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200971

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	900	CY	UNDERCUT EXCAVATION
0080000000-E	SP	300	TON	CLASS IV SUBGRADE STABILIZATION
0134000000-E	240	3,360	CY	DRAINAGE DITCH EXCAVATION
0141000000-E	240	300	LF	BERM DITCH CONSTRUCTION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	255	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0360000000-E	310	8	LF	12" RC PIPE CULVERTS, CLASS III
0366000000-E	310	912	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	80	LF	18" RC PIPE CULVERTS, CLASS III
0378000000-E	310	92	LF	24" RC PIPE CULVERTS, CLASS III
0384000000-E	310	28	LF	30" RC PIPE CULVERTS, CLASS III
0390000000-E	310	396	LF	36" RC PIPE CULVERTS, CLASS III
0396000000-E	310	540	LF	42" RC PIPE CULVERTS, CLASS III
0402000000-E	310	32	LF	48" RC PIPE CULVERTS, CLASS III
0408000000-E	310	180	LF	54" RC PIPE CULVERTS, CLASS III
0708000000-E	310	124	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	5	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0980000000-E	SP	208	LF	*** WELDED STEEL PIPE, *****" THICK, GRADE B, INSTALLED BY BORING & JACKING (15", 0.500")
0980000000-E	SP	256	LF	*** WELDED STEEL PIPE, *****" THICK, GRADE B, INSTALLED BY BORING & JACKING (36", 0.500")
0980000000-E	SP	60	LF	*** WELDED STEEL PIPE, *****" THICK, GRADE B, INSTALLED BY BORING & JACKING (54", 0.750")
0980000000-E	SP	76	LF	*** WELDED STEEL PIPE, *****" THICK, GRADE B, INSTALLED BY BORING & JACKING (72", 1.000")
0995000000-E	340	579	LF	PIPE REMOVAL
1110000000-E	510	450	TON	STABILIZER AGGREGATE
1121000000-E	520	1,815	TON	AGGREGATE BASE COURSE
1220000000-E	545	250	TON	INCIDENTAL STONE BASE
1297000000-E	607	3,900	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (2.5")
1489000000-E	610	250	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1491000000-E	610	4,300	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
1498000000-E	610	1,100	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1503000000-E	610	3,150	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C
1519000000-E	610	815	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1523000000-E	610	3,200	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C
1560000000-E	620	450	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1565000000-E	620	210	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
1891000000-E	SP	175	SY	GENERIC PAVING ITEM STREET PRINTING
2022000000-E	815	115	CY	SUBDRAIN EXCAVATION
2033000000-E	815	85	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2209000000-E	838	13	CY	ENDWALLS
2220000000-E	838	7.5	CY	REINFORCED ENDWALLS
2253000000-E	840	2.5	CY	PIPE COLLARS
2264000000-E	840	1.5	CY	PIPE PLUGS
2275000000-E	SP	25	CY	FLOWABLE FILL
2286000000-N	840	28	EA	MASONRY DRAINAGE STRUCTURES
2297000000-E	840	8.5	CY	MASONRY DRAINAGE STRUCTURES
2308000000-E	840	37	LF	MASONRY DRAINAGE STRUCTURES
2352000000-N	840	1	EA	FRAME WITH GRATE, STD 840.**** (840.16)
2366000000-N	840	8	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	7	EA	FRAME WITH TWO GRATES, STD 840.29
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
2374000000-N	840	4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
2396000000-N	840	4	EA	FRAME WITH COVER, STD 840.54
2440000000-N	840	6	EA	CONCRETE APRON FOR CATCH BASIN
2542000000-E	846	1,875	LF	1'-6" CONCRETE CURB & GUTTER
2549000000-E	846	150	LF	2'-6" CONCRETE CURB & GUTTER
2577000000-E	846	760	LF	CONCRETE EXPRESSWAY GUTTER
2598000000-E	848	25	SY	CONCRETE WHEELCHAIR RAMPS
2619000000-E	850	44	SY	4" CONCRETE PAVED DITCH
2647000000-E	852	425	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)
2724000000-E	857	280	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED
2739000000-E	852	1,125	SY	GENERIC PAVING ITEM 6" CONC ISLAND COVERS
2759000000-N	SP	6	EA	GENERIC PAVING ITEM HINGED METAL BOLLARDS
2830000000-N	858	6	EA	ADJUSTMENT OF MANHOLES
2995000000-N	SP	1	EA	GENERIC DRAINAGE ITEM CONVERT DI TO OTCB
3030000000-E	862	925	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3210000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3317000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77
3628000000-E	876	120	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	580	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	2,075	SY	FILTER FABRIC FOR DRAINAGE
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM PILE / PANEL WALL
4072000000-E	903	1,085	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4082200000-N	SP	Lump Sum		OVERHEAD SIGN ASSEMBLY AT STA ********* (19+50.00)
4082200000-N	SP	Lump Sum		OVERHEAD SIGN ASSEMBLY AT STA ********* (28+70.00)
4096000000-N	904	5	EA	SIGN ERECTION, TYPE D
4102000000-N	904	28	EA	SIGN ERECTION, TYPE E
4129000000-N	906	5	EA	RELOCATE SIGN, TYPE ***** (D)
4129000000-N	906	4	EA	RELOCATE SIGN, TYPE ***** (E)
4155000000-N	907	44	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4192000000-N	907	4	EA	DISPOSAL OF SUPPORT, U-CHANNEL
4400000000-E	1110	214	SF	WORK ZONE SIGNS (STATIONARY)
4405000000-E	1110	200	SF	WORK ZONE SIGNS (PORTABLE)
4410000000-E	1110	32	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4415000000-N	1115	2	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS
4430000000-N	1130	93	EA	DRUMS
4435000000-N	1135	50	EA	CONES
4445000000-E	1145	210	LF	BARRICADES (TYPE III)
4450000000-N	1150	224	HR	FLAGGER
4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
4485000000-E	1170	290	LF	PORTABLE CONCRETE BARRIER
4510000000-N	SP	300	HR	POLICE
4650000000-N	1251	2,508	EA	TEMPORARY RAISED PAVEMENT MARKERS
4810000000-E	1205	93,447	LF	PAINT PAVEMENT MARKING LINES (4")
4820000000-E	1205	636	LF	PAINT PAVEMENT MARKING LINES (8")
4835000000-E	1205	1,466	LF	PAINT PAVEMENT MARKING LINES (24")
4840000000-N	1205	96	EA	PAINT PAVEMENT MARKING CHARACTER
4845000000-N	1205	170	EA	PAINT PAVEMENT MARKING SYMBOL
4847000000-E	SP	23,144	LF	POLYUREA PAVEMENT MARKING LINES (4")
4847110000-E	SP	271	LF	POLYUREA PAVEMENT MARKING LINES (8")
4847140000-E	SP	366	LF	POLYUREA PAVEMENT MARKING LINES (24")
4847200000-N	SP	63	EA	POLYUREA PAVEMENT MARKING CHARACTER
4847220000-N	SP	42	EA	POLYUREA PAVEMENT MARKING SYMBOL

13-SEP-2004 15:11
E:\Proj\U4008.sum
Kroegland AI