

PROJECT NO.	SHEET NO.	TOTAL NO.
10CR.10841.3, 10CR.10841.4, 10CR.20841.6, ETC.		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER CONST SMI	SHOULDER RECONST SMI	DITCHING LF	1 1/2" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	6" DRIVEWAYS SY	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	SEED & MULCHING AC	
10CR.10841.3	Stanly	1	NC 200	FURR RD (SR 1121) TO SCL OF STANFIELD	1	2.1	23	63		2.1	840						2,618	525		189	420				1.53	
TOTAL FOR PROJ NO. 10CR.10841.3						2.1		63		2.1	840						2,618	525		189	420				1.53	
10CR.10841.4	Stanly	2	NC 24/27	PVMT JT AT RIVER HAVEN DR (SR 1778) TO GARRISON BRIDGE	1	0.69	24	21		0.92	140		270				1,380	173		94	173				0.50	
TOTAL FOR PROJ NO. 10CR.10841.4						0.69		21		0.92	140		270				1,380	173		94	173				0.50	
10CR.20841.6	Stanly	3	AUSTIN RD (SR 1214)	CANTON RD (SR 1249) TO NC 73	2	3.15	20	95		3.15	1,260				3,299	790			246						2.30	
TOTAL FOR PROJ NO. 10CR.20841.6						3.15		95		3.15	1,260		0		3,299	790	0	0	246							2.30
10CR.20841.7	Stanly	4	SOUTH STANLY SCHOOL RD (SR 1922)	NC 138 TO COTTONVILLE RD (SR 1918)	2	3.37	20	101		3.37	1,348				3,492	845			261						2.46	
TOTAL FOR PROJ NO. 10CR.20841.7						3.37		101		3.37	1,348		0		3,492	845	0	0	261							2.46
10CR.20841.8	Stanly	5	COLEY STORE RD (SR 1211)	ECL OF LOCUST TO BETHEL CH RD (SR 1200)	3	1.32	21	40	2.64		528			942	1,399	330			145			13			1.91	
TOTAL FOR PROJ NO. 10CR.20841.8						1.32		40	2.64	0	528		0	942	1,399	330			145			13				1.91
10CR.308401.4	Stanly	6	WEST MAIN ST (SR 1274)	WVCL OF ALBEMARLE TO BEGIN OF C & G	2	1.05	24	32		1.05	420		220		1323	263			96		263				0.77	
TOTAL FOR PROJ NO. 10CR.308401.4						1.05		32	0	1.05	420		220	0	1323	263			96		263					0.77
10CR.308401.3	Stanly	7	WEST MAIN ST (SR 1274)	BEGIN C & G TO NC 73	4	0.67	36					14,150	100		1,193				72		168					
TOTAL FOR PROJ NO. 10CR.308401.3						0.67		0	0	0	0	14,150	100	0	1,193	0	0	0	72		168					
10CR.308401.5	Stanly	8	EAST MAIN ST (SR 1625)	FIVE POINTS TO PEE DEE AVE	5	0.92	36					19,430			1,638				99		230					
TOTAL FOR PROJ NO. 10CR.308401.5						0.92		0	0	0	0	19,430	0	0	1,638	0	0	0	99		230					
10CR.308410.3	Stanly	9	COLEY STORE RD (SR 1211)	PVMT JT AT NC 24/27 TO ECL OF LOCUST	3	0.34	21	10	0.68		70			243	354	68			36			25			0.49	
TOTAL FOR PROJ NO. 10CR.308410.3						0.34		10	0.68	0	70	0	0	243	354	68			36			25				0.49
10CR.308419.3	Stanly	10	US 52	SOUTH OF WEST WHITLEY ST (SR 1933) TO END C & G	6	0.62	36						100				1,129	155		78	155		3	3		
TOTAL FOR PROJ NO. 10CR.308419.3						0.62		0	0	0	0	0	100	0	0	0	1,129	155		78	155		3	3		
10CR.308430.2	Stanly	11	NC 200	SCL OF STANFIELD TO RAILROAD TRACKS	1	1.17	23	35		1.17	468						1,458	295		106	234				0.85	
TOTAL FOR PROJ NO. 10CR.308430.2						1.17		35	0	1.17	468	0	0	0	0	0	1,458	295		106	234					0.85
GRAND TOTAL						15.4		397	3.32	11.76	5,074	33,580	690	1,185	12,698	2,296	6,585	1,148	955	467	1,643	38	3	3	10.81	