

PROJECT NO.	SHEET NO.	TOTAL NO.
11CR.10861.10, ETC.	8	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	2.5" MILLING SY	1 1/2" MILLING SY	INTERMED. COURSE, I19.0B TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	MANHOLES EA	METER OR VALVE BOX EA	PORTABLE LIGHTING LS	SEED & MULCHING AC	TRENCHING (PAVED) LF	TRENCHING (UNPAVED) LF	INDUCTIVE LOOP LF		
11CR.10861.10	Surry	1	NC 89	FROM SR 1338 TO 100 FEET SOUTH OF SR 1452	5	2.69	20	200	5.38	31,563		4545			2,768		380					2.69					
		2	NC 89	FROM US 52 BUS. TO SR 1753	3	0.9	20	60	1.8							1,093		66					0.90				
TOTAL FOR PROJ NO. 11CR.10861.10						3.59		260	7.18	31,563		4545			3,861		446					3.59					
11CR.20861.10	Surry	3	SR 1144	FROM NCL ELKIN TO NC 268	3	1.57	24	40	3.14						1,867		112				3	1.57					
		4	SR 1345	FROM 601 BUSINESS TO 500 FEET NORTH SR 1350	188	1.2	20	50	2.4			889		1,265				82					1.20				
		5	SR 1350	FROM 50 FEET WEST OF SR 1544 TO SR 1387	3	1	20	60	2							1,017		61					1.00				
		6	SR 1395	FROM NC 89 TO SR 1350	3	1	20	100	2							1,092		66					1.00				
		7	SR 1774	FROM SR 1815 TO SR 1775	1	1.6	22	60	3.2					1,735	500			145					1.60				
		8	SR 1775	FROM SR 1774 TO SR 1776	1	0.18	20	10	0.36					215				14					0.18				
		9	SR 1776	FROM SR 1775 TO NC 89	1	0.71	18	50	1.42					643	150			52					0.71				
		10	SR 2015	FROM SR 2119 TO SR 2012	188	1.6	20	150	3.2			889		1,580				103					1.60				
		11	SR 2019	FROM SR 2038 TO SR 2012	388	3.9	20	400	7.8			889					4,078		245				3.90				
		12	SR 2258	FROM 50 FEET SOUTH OF SR 1359 TO SR 1356	3	1.9	18	150	3.8								1,857		111				1.90				
		13	SR 2258	FROM 50 FEET SOUTH OF SR 2218 TO US 601	3	1.7	18	115	3.4								1,518		91				1.70				
		TOTAL FOR PROJ NO. 11CR.20861.10						16.36		1185	32.72	0	2,667	0	5,438	650	11,429		1,082			3		16.36			
		11CR.308609.10	Surry	14	SR 1144	ELKIN: FROM 520 FEET SOUTH OF NC 268 BYPASS TO NCL ELKIN	3	0.3	24	30	0.6						357		21				2	0.30			
15	SR 1149			ELKIN: FROM US 21 BUS. TO BRIDGE OVER BIG ELKIN CREEK	4	0.3	40					7,040				593		36		3	2	1		50	50	500	
TOTAL FOR PROJ NO. 11CR.308609.10						0.6		30	0.6	0	7,040	0	0	950		57		3	4	1	0.30	50	50	500			
11CR.308617.10	Surry	16	SR 1670	MOUNT AIRY: FROM US 52 BUSINESS TO NC 104	7	0.3	48			8,448					1,188		71		1	7	1		25	25	250		
		17	SR 1727	MOUNT AIRY: FROM SR 1708 TO NC 104	2	0.5	28						680				44		14	7							
		TOTAL FOR PROJ NO. 11CR.308617.10						0.8		0	0	8,448	0	0	680	0	1,188	44	71	15	14	1		25	25	250	
11CR.10991.10	Yadkin	18	NC 67	FROM SR 1526 TO SR 1570	3	1.75	20	168	3.5						1,776		107					1.75					
		TOTAL FOR PROJ NO. 11CR.10991.10						1.75		168	3.5	0	0	0	0	1,776	0	107	0	0	0	0	1.75				
11CR.20991.10	Yadkin	19	SR 1003	FROM SR 1541 TO SURRY COUNTY	388	3.67	20	342	7.34		444				3,760		226					3.67					
		20	SR 1314	FROM US 21 TO SR 1141	3	3.6	20	234	7.2							3,750		225				3.60					
		21	SR 1432	FROM SOUTH CITY LIMITS JONESVILLE TO END OF MAINTENANCE	3	0.28	24	10	0.56							333		20					0.56				
		22	SR 1506	FROM SR 1503 TO SR 1510	3	0.63	20	12	1.26							665		40					0.63				
		23	SR 1510	FROM SR 1506 TO SR 1585	3	0.1	20		0.2							99		6					0.10				
		24	SR 1570	FROM SR 1605 TO EOP	388	0.75	24	84	1.5			1,067				892		53					0.75				
		25	SR 1640	FROM SR 1605 TO END OF MAINTENANCE	1	0.36	18	10	0.72					315				21					0.36				
TOTAL FOR PROJ NO. 11CR.20991.10						9.39		692	18.78	0	1,511	0	315	0	9,499	0	591	0	0	0	0	9.67					
11CR.309930.10	Yadkin	26	SR 1605	YADKINVILLE: FROM 50' EAST OF US 601 TO SR 1700	7	0.18	44			4,646					654		39		2	3	1						
		"	"	YADKINVILLE: FROM SR 1700 TO SR 1634	6	0.53	24		1.06	7,462					1,054		63		6	6							
		TOTAL FOR MAP NO. 26						0.71		0	1.06	12,108	0	0	0	1,708	0	102	8	9	1						
TOTAL FOR PROJ NO. 11CR.309930.10						0.71		0	1.06	12,108	0	0	0	0	1,708	0	102	8	9	1							
GRAND TOTAL						33.2		2,335	63.84	52,119	11,218	4,545	6,433	650	27,515	2,896	2,327	173	26	30	3	31.67	75	75	750		