PROJ. REFERENCE NO.	SHEET NO.
B-3375	EW-Volume-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Sheet No.'s
32+50.000	0	0	X-1
32+80.830	23	6	X-1
33+00.000	28	8	X-2
33+50.000	75	43	X-2
34+00.000	57	65	X-2
34+50.000	30	84	X-3
35+00.000	8	127	X-3
35+50.000	3	169	X-3
36+00.000	2	200	X-3
36+50.000	2	250	X-3
37+00.000	2	311	X-4
37+50.000	2	374	X-4
38+00.000	2	403	X-4
38+50.000	11	478	X-4
39+00.000	38	584	X-4
39+50.000	28	1146	X-5
40+00.000	0	1814	X-5
40+50.000	0	1548	X-5
41+00.000	0	1074	X-5
41+50.000	0	933	X-6
42+00.000	0	738	X-6
42+50.000	0	617	X-6
45+00.000	8	621	X-7
45+50.000	24	112	X-8
46+00.000	19	72	X-8
46+50.000	33	67	X-8
47+00.000	137	42	X-8
47+50.000	235	18	X-9
48+00.000	245	33	X-9
48+50.000	207	47	X-9
49+00.000	222	31	X-9
49+50.000	212	12	X-10
50+00.000	151	19	X-10
50+50.000	91	15	X-10
51+00.000	39	24	X-10
51+50.000	33	55	X-11
52+00.000	54	65	X-11
52+50.000	76	62	X-11
53+00.000	45	73	X-11
53+50.000	42	83	X-12
54+00.000	64	79	X-12
54+50.000	43	76	X-12
55+00.000	48	98	X-12
55+50.000	62	118	X-13
56+00.000	114	74	X-13
56+22.170	60	11	X-13