CH ENGINEERING
PO BOX 30128 RALEIGH, NC 27622
TELE 919.788.0224
FAX 919.788.0232

PROJ. REFERENCE NO.	SHEET NO.
B-3375	PM-1

FINAL PAVEMENT MARKING PLAN

FINAL PAVEMENT MARKING SCHEDULE AND QUANTITIES

SYMBOL	DESCRIPTION	PAY ITEM/ QUANTITY BREAKDOWN		TOTAL QUANTITY	
		PAVEMENT MARKING LINES			
		THERMOPLASTIC (4", 90 mils)			
TA	WHITE EDGELINE	4003	ft.		
			TOTAL	4003	ft.
		THERMOPLASTIC (4", 120 mils)			
TC	10 ft. WHITE SKIP	20	ft.		
TD	2 ft. WHITE MINISKIP	34	ft.		
TE	WHITE SOLID LANE LINE	192	ft.		
TF	10 ft. YELLOW SKIP	656	ft.		
TH	YELLOW SINGLE CENTER LINE	2541	ft.		
TI	YELLOW DOUBLE CENTER LINE	2784	ft.		
			TOTAL	6227	ft.
		THERMOPLASTIC (8", 90 mils)			
TT	YELLOW DIAGONAL	130	ft.		
			TOTAL	130	ft.
		COLD APPLIED PLASTIC (4")			
CA	WHITE EDGELINE	494	ft.		
CD	2 ft. WHITE MINISKIP	12	ft.		
CE	WHITE SOLID LANE LINE	20	ft.		
CF	10 ft. YELLOW SKIP	60	ft.		
CH	YELLOW SINGLE CENTER LINE	246	ft.		
CI	YELLOW DOUBLE CENTER LINE	258	ft.		
			TOTAL	1090	ft.
		PAVEMENT MARKING SYMBOLS			
		THERMOPLASTIC THICK SYMBOL (90 mils)			
UA	LEFT TURN ARROW	7	EA		
UB	RIGHT TURN ARROW	2	EA		
UC	STRAIGHT ARROW	3	EA		
			TOTAL	12	EA
		COLD APPLIED PLASTIC SYMBOL			
DA	LEFT TURN ARROW	1	EA		
DC	STRAIGHT ARROW	1	EA		
			TOTAL	2	EA
		PAVEMENT MARKERS			
		PERMANENT RAISED			
MA	YELLOW & YELLOW	108	EA		
MB	CRYSTAL & RED	13	EA		
			TOTAL	121	EA

NORTH CAROLINA PROFESSIONAL SEAL 21047 ENGINEER KELLIN W. BISBY
10-11-2004

FINAL PAVEMENT MARKINGS

SCALE:	NONE
DATE:	4/2004
DWG. BY:	KWB
DESIGN BY:	KWB
REVIEWED BY:	TRH

DIVISION OF HIGHWAYS TRANSPORTATION BUILDING RALEIGH, NORTH CAROLINA

REVISIONS

CADD FILE

10/11/2004