

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201165

# SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (43+81.84-L-)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	500	CY	UNDERCUT EXCAVATION
0080000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZA- TION
0106000000-E	230	13,450	CY	BORROW EXCAVATION
0134000000-E	240	21	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0199000000-E	SP	500	SF	TEMPORARY SHORING
0318000000-E	300	116	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	180	LF	15" SIDE DRAIN PIPE
0344000000-E	310	100	LF	18" SIDE DRAIN PIPE
0345000000-E	310	104	LF	24" SIDE DRAIN PIPE
0366000000-E	310	296	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	72	LF	18" RC PIPE CULVERTS, CLASS III
0378000000-E	310	300	LF	24" RC PIPE CULVERTS, CLASS III
0708000000-E	310	36	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	812	LF	PIPE REMOVAL
1220000000-E	545	75	TON	INCIDENTAL STONE BASE
1330000000-E	607	270	SY	INCIDENTAL MILLING
1489000000-E	610	2,575	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	2,105	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	2,125	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	350	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2275000000-E	SP	0.91	CY	FLOWABLE FILL
2286000000-N	840	7	EA	MASONRY DRAINAGE STRUCTURES
2364000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.16
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
2374000000-N	840	1	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
2549000000-E	846	460	LF	2'-6" CONCRETE CURB & GUTTER
2556000000-E	846	410	LF	SHOULDER BERM GUTTER
3030000000-E	862	650	LF	STEEL BM GUARDRAIL
3045000000-E	862	50	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3360000000-E	863	912.5	LF	REMOVE EXISTING GUARDRAIL
3628000000-E	876	80	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	930	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	3,195	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON

ItemNumber	Sec #	Quantity	Unit	Description
3984000000-E	SP	1,564	SF	GENERIC WALL ITEM TEMPORARY FABRIC WALL
4412000000-E	SP	104	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	192	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	36	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	70	EA	DRUMS
4435000000-N	1135	50	EA	CONES
4446100000-E	SP	48	LF	BARRICADES (TYPE III)
4455000000-N	1150	130	MD	FLAGGER
4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
4475000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)
4485000000-E	1170	520	LF	PORTABLE CONCRETE BARRIER
4490000000-E	1170	250	LF	PORTABLE CONCRETE BARRIER (ANCHORED)
4615000000-E	1205	988	LF	REMOVABLE TAPE PAVEMENT MARK- ING LINES (4")
4650000000-N	1251	58	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-E	1205	4,003	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	6,227	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4695000000-E	1205	130	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
4725000000-E	1205	12	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
4770000000-E	1205	1,090	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4")
4805000000-N	1205	2	EA	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL
4810000000-E	1205	17,006	LF	PAINT PAVEMENT MARKING LINES (4")
4835000000-E	1205	52	LF	PAINT PAVEMENT MARKING LINES (24")
4900000000-N	1252	121	EA	PERMANENT RAISED PAVEMENT MARKERS

ItemNumber	Sec #	Quantity	Unit	Description
6000000000-E	1605	1,950	LF	TEMPORARY SILT FENCE
6006000000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	835	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	400	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	4.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	100	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	200	LF	SAFETY FENCE
6030000000-E	1630	2,500	CY	SILT EXCAVATION
6036000000-E	1631	2,300	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	200	LF	1/4" HARDWARE CLOTH
6045000000-E	SP	75	LF	*** TEMPORARY PIPE (24")
6069000000-E	1638	240	CY	STILLING BASINS
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	5	ACR	SEEDING & MULCHING
6087000000-E	1660	2.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	3.75	TON	FERTILIZER TOPDRESSING
6111000000-E	SP	225	LF	IMPERVIOUS DIKE
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
6120000000-E	SP	250	CY	CULVERT DIVERSION CHANNEL