

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (43+81.84-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0106000000-E	230	BORROW EXCAVATION	13,450 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	21 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	500 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	116 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	180 LF		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	100 LF		
0016	0345000000-E	310	24" SIDE DRAIN PIPE	104 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	296 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0019	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	300 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	36 LF		
0021	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0022	0995000000-E	340	PIPE REMOVAL	812 LF		
0023	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0024	1330000000-E	607	INCIDENTAL MILLING	270 SY		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,575 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,105 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,125 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	350 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0030	2275000000-E	SP	FLOWABLE FILL	0.91 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0032	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	460 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2556000000-E	846	SHOULDER BERM GUTTER	410	LF	
0038	3030000000-E	862	STEEL BM GUARDRAIL	650	LF	
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50	LF	
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
0044	3360000000-E	863	REMOVE EXISTING GUARDRAIL	912.5	LF	
0045	3628000000-E	876	PLAIN RIP RAP, CLASS I	80	TON	
0046	3649000000-E	876	PLAIN RIP RAP, CLASS B	930	TON	
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,195	SY	
0048	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
0049	3984000000-E	SP	GENERIC WALL ITEM TEMPORARY FABRIC WALL	1,564	SF	
0050	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	104	SF	
0051	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	192	SF	
0052	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	36	SF	
0053	4430000000-N	1130	DRUMS	70	EA	
0054	4435000000-N	1135	CONES	50	EA	
0055	4446100000-E	SP	BARRICADES (TYPE III)	48	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4455000000-N	1150	FLAGGER	130		MD
0057	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2		EA
0058	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	2		EA
0059	4485000000-E	1170	PORTABLE CONCRETE BARRIER	520		LF
0060	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	250		LF
0061	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (4")	988		LF
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	58		EA
0063	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,003		LF
0064	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,227		LF
0065	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	130		LF
0066	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12		EA
0067	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4")	1,090		LF
0068	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL	2		EA
0069	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,006		LF
0070	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	52		LF
0071	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	121		EA
0072	6000000000-E	1605	TEMPORARY SILT FENCE	1,950		LF

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0074	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	835 TON		
0075	6012000000-E	1610	SEDIMENT CONTROL STONE	400 TON		
0076	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0077	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0078	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0079	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0080	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0081	6029000000-E	SP	SAFETY FENCE	200 LF		
0082	6030000000-E	1630	SILT EXCAVATION	2,500 CY		
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,300 SY		
0084	6042000000-E	1632	1/4" HARDWARE CLOTH	200 LF		
0085	6045000000-E	SP	*** TEMPORARY PIPE (24")	75 LF		
0086	6069000000-E	1638	STILLING BASINS	240 CY		
0087	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0088	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0089	6087000000-E	1660	MOWING	2.5 ACR		
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0094	6111000000-E	SP	IMPERVIOUS DIKE	225 LF		
0095	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0096	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	16 EA		
0097	6120000000-E	SP	CULVERT DIVERSION CHANNEL	250 CY		

CULVERT ITEMS

0098	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (40+04.00 -L-)	Lump Sum	L.S.	
0099	8126000000-N	414	CULVERT EXCAVATION, STA ***** (40+04.00 -L-)	Lump Sum	L.S.	
0100	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	110 TON		
0101	8196000000-E	420	CLASS A CONCRETE (CULVERT)	159.3 CY		
0102	8245000000-E	425	REINFORCING STEEL (CULVERT)	26,788 LB		
0103	8590000000-E	876	PLAIN RIP RAP, CLASS ** (1)	49 TON		
0104	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	54 SY		

STRUCTURE ITEMS

0105	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (43+81.84 -L-)	Lump Sum	L.S.	
0106	8096000000-E	SP	PILE EXCAVATION IN SOIL	57 LF		
0107	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	378.1 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	40 LF		
0109	8113000000-N	SP	SID INSPECTION	12 EA		
0110	8114000000-N	SP	SPT TESTING	12 EA		
0111	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
0112	8116000000-E	SP	CSL TUBES	1,792.4 LF		
0113	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,254 SF		
0114	8161000000-E	420	GROOVING BRIDGE FLOORS	10,519 SF		
0115	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	149.7 CY		
0116	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (43+81.84 -L-)	Lump Sum	L.S.	
0117	8217000000-E	425	REINFORCING STEEL (BRIDGE)	74,213 LB		
0118	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	9,351 LB		
0119	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	396,100 LS		
0120	8364000000-E	450	HP12X53 STEEL PILES	57 LF		
0121	8475000000-E	460	TWO BAR METAL RAIL	322.06 LF		
0122	8517000000-E	460	1'-**X ***** CONCRETE PARA-PET (1'-2" X 3'-3")	339.06 LF		
0123	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0124	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

C201165 (B-3375)
Wake County

2/16/99

Contract No: C201165
County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General