

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200488

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+90.00)
0043000000-N	226	Lump Sum		GRADING
0050000000-M	226	0.4	HA	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-M	226	200	M3	UNDERCUT EXCAVATION
0134000000-M	240	145	M3	DRAINAGE DITCH EXCAVATION
0195000000-M	265	100	M3	SELECT GRANULAR MATERIAL
0196000000-M	270	100	M2	FABRIC FOR SOIL STABILIZATION
0318000000-M	300	58	MTN	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-M	310	30	M	375MM SIDE DRAIN PIPE
0344000000-M	310	15.6	M	450MM SIDE DRAIN PIPE
0372000000-M	310	122.6	M	450MM RC PIPE CULVERTS, CLASS III
0588000000-M	310	7.2	M	450MM CS PIPE CULVERTS, 1.63MM THICK
0708000000-M	310	8.4	M	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK
0806000000-M	310	2	EA	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK
0995000000-M	340	75.6	M	PIPE REMOVAL
1121000000-M	520	1,530	MTN	AGGREGATE BASE COURSE
1220000000-M	545	75	MTN	INCIDENTAL STONE BASE
1489000000-M	610	546	MTN	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-M	610	801	MTN	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-M	610	775	MTN	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-M	620	108	MTN	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-M	654	75	MTN	ASPHALT PLANT MIX PAVEMENT REPAIR
2000000000-N	806	7	EA	RIGHT OF WAY MARKERS

ItemNumber	Sec #	Quantity	Unit	Description
2022000000-M	815	55.2	M3	SUBDRAIN EXCAVATION
2033000000-M	815	41.4	M3	SUBDRAIN FINE AGGREGATE
2044000000-M	815	100	M	150MM PERFORATED SUBDRAIN PIPE
2055000000-M	815	9	EA	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-M	815	2	M	150MM OUTLET PIPE (SUBDRAINS)
2253000000-M	840	0.66	M3	PIPE COLLARS
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2366000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-M	846	21	M	SHOULDER BERM GUTTER
3030000000-M	862	80.01	M	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3380000000-M	862	76.2	M	TEMPORARY STEEL BM GUARDRAIL
3387000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)
3389100000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
3649000000-M	876	142	MTN	PLAIN RIP RAP, CLASS B
3656000000-M	876	670	M2	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	4	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4400000000-M	1110	14	M2	WORK ZONE SIGNS (STATIONARY)
4405000000-M	1110	9	M2	WORK ZONE SIGNS (PORTABLE)
4410000000-M	1110	4	M2	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	20	EA	DRUMS

ItemNumber	Sec #	Quantity	Unit	Description
4435000000-N	1135	17	EA	CONES
4445000000-M	1145	100	M	BARRICADES (TYPE III)
4450000000-N	1150	32	HR	FLAGGER
4650000000-N	1251	76	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-M	1205	850	M	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)
4686000000-M	1205	850	M	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)
4810000000-M	1205	5,340	M	PAINT PAVEMENT MARKING LINES (100MM)
4900000000-N	1252	40	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-M	1505	22	MTN	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
5306000000-M	SP	22	MTN	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
5714000000-M	1520	24.8	M	***MM DI SEWER PIPE, CLASS *** (200MM, 50 2.41 MPA WP)
5714000000-M	1520	69.5	M	***MM DI SEWER PIPE, CLASS *** (450MM, 50 2.41MPA WP)
5776000000-M	1525	1	EA	150MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH
5780000000-M	1525	1.6	M	PRECAST CONC MANHOLE WALL, ***MM DIA, OVER 1.8M HT (1500M)
5798000000-M	1530	76	M	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (450MM, CLAY SEWER PIPE)
5816000000-N	1530	2	EA	BREAK DOWN, PLUG, & FILL ABANDONED UTILITY MANHOLE
6000000000-M	1605	300	M	TEMPORARY SILT FENCE
6006000000-M	1610	100	MTN	STONE FOR EROSION CONTROL, CLASS A
6009000000-M	1610	800	MTN	STONE FOR EROSION CONTROL, CLASS B
6012000000-M	1610	230	MTN	SEDIMENT CONTROL STONE
6015000000-M	1615	1.5	HA	TEMPORARY MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6018000000-M	1620	75	KG	SEED FOR TEMPORARY SEEDING
6021000000-M	1620	0.5	MTN	FERTILIZER FOR TEMPORARY SEEDING
6029000000-M	SP	100	M	SAFETY FENCE
6030000000-M	1630	2,100	M3	SILT EXCAVATION
6036000000-M	1631	1,300	M2	MATTING FOR EROSION CONTROL
6038000000-M	SP	90	M2	PERMANENT SOIL REINFORCEMENT MAT
6042000000-M	1632	20	M	6.4MM HARDWARE CLOTH
6084000000-M	1660	1.5	HA	SEEDING & MULCHING
6087000000-M	1660	1	HA	MOWING
6090000000-M	1661	25	KG	SEED FOR REPAIR SEEDING
6093000000-M	1661	0.25	MTN	FERTILIZER FOR REPAIR SEEDING
6096000000-M	1662	50	KG	SEED FOR SUPPLEMENTAL SEEDING
6108000000-M	1665	2.25	MTN	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
6123000000-M	1670	0.75	HA	REFORESTATION

6/15/99

RD214495 - Nov 03 03:33:36 - WAKabiDavis