

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-M	225	UNCLASSIFIED EXCAVATION	5,600 M3		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+47.813)	Lump Sum	L.S.	
0004	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0005	0057000000-M	226	UNDERCUT EXCAVATION	500 M3		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 MTN		
0008	0134000000-M	240	DRAINAGE DITCH EXCAVATION	50 M3		
0009	0195000000-M	265	SELECT GRANULAR MATERIAL	1,000 M3		
0010	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	1,000 M2		
0011	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	33 MTN		
0012	0345000000-M	310	600MM SIDE DRAIN PIPE	10.8 M		
0013	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	2.4 M		
0014	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	19.2 M		
0015	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	19.2 M		
0016	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	50.4 M		
0017	0995000000-M	340	PIPE REMOVAL	49.8 M		
0018	1121000000-M	520	AGGREGATE BASE COURSE	100 MTN		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-M	545	INCIDENTAL STONE BASE	80	MTN	
0020	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,040	MTN	
0021	1525000000-M	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	440	MTN	
0022	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	74	MTN	
0023	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	16	MTN	
0024	2000000000-N	806	RIGHT OF WAY MARKERS	20	EA	
0025	2022000000-M	815	SUBDRAIN EXCAVATION	221	M3	
0026	2033000000-M	815	SUBDRAIN FINE AGGREGATE	100	M3	
0027	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	240	M	
0028	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	24	EA	
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2	EA	
0030	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	4	M	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0033	2556000000-M	846	SHOULDER BERM GUTTER	15	M	
0034	3030000000-M	862	STEEL BM GUARDRAIL	80.01	M	
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3559000000-M	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	160 M		
0039	3649000000-M	876	PLAIN RIP RAP, CLASS B	25 MTN		
0040	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	664 M2		
0041	4412000000-M	SP	WORK ZONE SIGNS (STATIONARY)	8 M2		
0042	4412100000-M	SP	WORK ZONE SIGNS (PORTABLE)	9 M2		
0043	4412200000-M	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	6 M2		
0044	4430000000-N	1130	DRUMS	30 EA		
0045	4446100000-M	SP	BARRICADES (TYPE III)	24 M		
0046	4450000000-N	1150	FLAGGER	64 HR		
0047	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	3,248 M		
0048	6000000000-M	1605	TEMPORARY SILT FENCE	300 M		
0049	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	70 MTN		
0050	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	405 MTN		
0051	6012000000-M	1610	SEDIMENT CONTROL STONE	410 MTN		
0052	6015000000-M	1615	TEMPORARY MULCHING	1 HA		
0053	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	50 KG		
0054	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 MTN		
0055	6024000000-M	1622	TEMPORARY SLOPE DRAINS	30 M		
0056	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6029000000-M	SP	SAFETY FENCE	230 M		
0058	6030000000-M	1630	SILT EXCAVATION	1,515 M3		
0059	6036000000-M	1631	MATTING FOR EROSION CONTROL	700 M2		
0060	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	500 M2		
0061	6042000000-M	1632	6.4MM HARDWARE CLOTH	30 M		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0063	6084000000-M	1660	SEEDING & MULCHING	1 HA		
0064	6087000000-M	1660	MOWING	0.5 HA		
0065	6090000000-M	1661	SEED FOR REPAIR SEEDING	25 KG		
0066	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25 MTN		
0067	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	50 KG		
0068	6108000000-M	1665	FERTILIZER TOPDRESSING	1.75 MTN		
0069	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0070	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0071	6123000000-M	1670	REFORESTATION	0.15 HA		

---

**STRUCTURE ITEMS**


---

0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (12+48.000 -L-)	Lump Sum	L.S.	
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+48.000 -L-)	Lump Sum	L.S.	

---

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8105520000-M	SP	914MM DIA DRILLED PIERS IN SOIL	59.7 M		
0075	8105620000-M	SP	914MM DIA DRILLED PIERS NOT IN SOIL	16.6 M		
0076	8111200000-M	SP	PERMANENT STEEL CASING FOR 914MM DRILLED PIER	45.1 M		
0077	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		
0078	8116000000-M	SP	CSL TUBES	335.8 M		
0079	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	62.8 M3		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+48.000 -L-)	Lump Sum	L.S.	
0081	8217000000-M	425	REINFORCING STEEL (BRIDGE)	11,583 KG		
0082	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,115 KG		
0083	8364000000-M	450	HP310X79 STEEL PILES	121.5 M		
0084	8391000000-N	450	STEEL PILE POINTS	18 EA		
0085	8503000000-M	460	CONCRETE BARRIER RAIL	115.164 M		
0086	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	465 MTN		
0087	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	475 M2		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8762000000-M	430	914MM X 533MM PRESTRESSED CONC CORED SLABS	689.4 M		

0806/Jan07/Q36500.424/D383647840000/E89

Total Amount Of Bid For Entire Project :

C201120 (B-3266)  
Wilkes County

2/16/99

Contract No: C201120  
County: Wilkes

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General