

**EROSION CONTROL****Seeding And Mulching:**

(5)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

January 1 - December 31

50# (55kg) Tall Fescue  
 5# (6kg) Centipede  
 50# (55kg) Pensacola Bahiagrass  
 500# (560kg) Fertilizer  
 4000# (4500kg) Limestone

Slopes 2:1 and Steeper and Waste and Borrow Locations:

January 1 - December 31

75# (85kg) Tall Fescue  
 50# (55kg) Pensacola Bahiagrass  
 500# (560kg) Fertilizer  
 4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Add 10# (12kg) Kobe or Korean Lespedeza to the above mixtures May 1 - August 31.

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza

January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.