

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201187														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	205500000-E	815	3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	443500000-N	1135	100	EA	CONES
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	444610000-E	SP	144	LF	BARRICADES (TYPE III)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+37.00)	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	445000000-N	1150	150	HR	FLAGGER
004300000-N	226	Lump Sum		GRADING	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	468500000-E	1205	72,852	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	468600000-E	1205	72,852	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
005700000-E	226	150	CY	UNDERCUT EXCAVATION	236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	471000000-E	1205	24	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
013400000-E	240	115	CY	DRAINAGE DITCH EXCAVATION	255600000-E	846	45	LF	SHOULDER BERM GUTTER	490000000-N	1252	457	EA	PERMANENT RAISED PAVEMENT MARKERS
019500000-E	265	100	CY	SELECT GRANULAR MATERIAL	303000000-E	862	475	LF	STEEL BM GUARDRAIL	600000000-E	1605	590	LF	TEMPORARY SILT FENCE
019600000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	600600000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
031800000-E	300	9	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	600900000-E	1610	190	TON	STONE FOR EROSION CONTROL, CLASS B
034300000-E	310	32	LF	15" SIDE DRAIN PIPE	327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	601200000-E	1610	330	TON	SEDIMENT CONTROL STONE
070800000-E	310	52	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	350300000-E	866	151	LF	WOVEN WIRE FENCE, 47" FABRIC	601500000-E	1615	1	ACR	TEMPORARY MULCHING
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	350900000-E	866	7	EA	4" TIMBER FENCE POSTS, 7'-6" LONG	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
099500000-E	340	30	LF	PIPE REMOVAL	351500000-E	866	7	EA	5" TIMBER FENCE POSTS, 8'-0" LONG	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
122000000-E	545	50	TON	INCIDENTAL STONE BASE	364900000-E	876	50	TON	PLAIN RIP RAP, CLASS B	602400000-E	1622	30	LF	TEMPORARY SLOPE DRAINS
148900000-E	610	495	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	365600000-E	876	940	SY	FILTER FABRIC FOR DRAINAGE	602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
149800000-E	610	410	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	365900000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	602900000-E	SP	200	LF	SAFETY FENCE
152500000-E	SP	450	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	402500000-E	901	15	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	603000000-E	1630	885	CY	SILT EXCAVATION
156000000-E	620	70	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	407200000-E	903	39	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	603600000-E	1631	1,130	SY	MATting FOR EROSION CONTROL
169300000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	410200000-N	904	3	EA	SIGN ERECTION, TYPE E	604200000-E	1632	40	LF	1/4" HARDWARE CLOTH
200000000-N	806	13	EA	RIGHT OF WAY MARKERS	415500000-N	907	9	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	607000000-N	SP	12	EA	SPECIAL STILLING BASINS
202200000-E	815	23	CY	SUBDRAIN EXCAVATION	441200000-E	SP	513	SF	WORK ZONE SIGNS (STATIONARY)	608400000-E	1660	1	ACR	SEEDING & MULCHING
203300000-E	815	17	CY	SUBDRAIN FINE AGGREGATE	441210000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	608700000-E	1660	1	ACR	MOWING
204400000-E	815	100	LF	6" PERFORATED SUBDRAIN PIPE	441220000-E	SP	142	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
					443000000-N	1130	20	EA	DRUMS	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
										609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
										610800000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
										611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
										611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99