

PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10361.2, ETC.	15	19

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECON. SMI	1½" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	ULTRATHIN ASPHALT TYPE B TONS	PG 64-22 PLANT MIX TONS	PG 70-28 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	APPLICATION OF ULTRATHIN SY	WHEELCHAIR RAMPS EA	ADJUST CATCH BASIN EA	ADJUST DROP INLET EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA		
12CR.10361.2	Gaston	1	NC 150	CLEVELAND CO TO CHERRYVILLE CL	2	1.16	24	10	2.32				1,509	10		91		40								
		2	NC 274	SC STATELINE TO SR 2435	2	2.12	20	10	4.24				2,299	20		139		50								
		3	NC 273	SR 1992 TO NC 16	2	2.28	VAR. 24-36	40	4.56				3,084	20		187		20								
		4	NC 275	STANLEY C.L. TO DALLAS C.L.	2	4.5	24	90	9.00		400		5,854	39		354		100								
TOTAL FOR PROJ NO. 12CR.10361.2						10.06		150	20.12		400		12,746	89		771		210								
12CR.20361.3	Gaston	5	SR 1108	SR 1109 TO SC STATELINE	5	1.11	20	20			400	650	1,204	35		103		60								
		6	SR 1153	US 321 TO SR 1136	1	0.8	VAR. 20-32	10					1,128	40		70		70								
		7	SR 1456	NC 275 TO NC 279	5	3.01	20	40			410	1,800	3,264	50		276		140								
		8	SR 1408	NC 274 TO SR 1401	1	1.64	18				400		1,689	30		103		45								
		9	SR 1113	SR 1126 TO END OLD PVT	1	0.8	18	10					824	15		50		20								
		10	SR 2532	NC 273 TO DEAD END	9	0.91	20	5					987	20		61		100								
TOTAL FOR PROJ NO. 12CR.20361.3						8.27		85	0.00		1,210	2,450	9,096	190		663		435								
12CR.303601.2	Gaston	11	NC 7	SR 2093 TO US 29/74	6	0.28	VAR. 44-60						835			50		20						2	3	
TOTAL FOR PROJ NO. 12CR.303601.2						0.28		0	0.00		0	0	835			50		20					2	3		
12CR.303606.1	Gaston	12	SR 1634	SR 1637 TO CHERRYVILLE CL	2	1.15	24	10					1,496	30		92		60								
TOTAL FOR PROJ NO. 12CR.303606.1						1.15		10	0.00		0	0	1,496	30		92		60								
12CR.303613.2	Gaston	13	NC 274	SR 2466 TO NIBLICK DR	11	1.1	VAR. 44-60			28,400			2,711	200		175		300			9		10		4	
		14	NC 7	NC 279 TO SR 2200	3	0.65	44																			
		15	SR 2278	CL GASTONIA TO BOXWOOD DR	2	0.89	VAR. 44-60		1.78				2,340	35		143		40					14		3	
		16	US 29/74	US 321S TO NC 274	7	0.5	62			18,187	600		1,158	30		72		60					2		2	
TOTAL FOR PROJ NO. 12CR.303613.2						3.34		0	1.78	46,587	600	0	6,209	265		440	390	26	405		9		49		14	
12CR.303623.2	Gaston	17	NC 7	LOWELL WCL TO SR 2329	3	1.34	VAR. 44-60						3,196	50		195		200			6		1	15	4	
TOTAL FOR PROJ NO. 12CR.303623.2						1.34		0	0.00	0	0	0	3,196	50		195		200			6		1	15	4	
12CR.303627.2	Gaston	18	NC 273	TUCKASEEGEE RD TO RR TRACKS	2	1.22	VAR. 24-44		1.60				2,521	70		156		30					5		4	
		19	SR 2093	NC 7 TO RR TRACKS	1	0.33	VAR. 22-26						899			54		30								
TOTAL FOR PROJ NO. 12CR.303627.2						1.75		0	1.60	0	1,110	0	3,420	70		210		60					5		4	
12CR.303638.1	Gaston	20	SR 2505	SR 2490 TO SR 2209	3	0.31	VAR. 19-20																			
		4			4	0.12	VAR. 22-23																			
		9			9	0.17	24																			
		10			10	0.63	VAR. 18-20	10					1,550	40		96		30			14	1	4		2	
TOTAL FOR PROJ NO. 12CR.303638.1						1.3		10	0.00	0	0	0	1,550	40		96		30			14	1	4		2	
12CR.303637.1	Gaston	22	NC 7	SR 2200 TO LOWELL WCL	3	0.65	44						1,927	25		117		100			2	1	8		2	
TOTAL FOR PROJ NO. 12CR.303637.1						0.79		0	0.00	0	0	0	1,927	25		117		100			2	1	8		2	
12CR.303695.1	Gaston	21	US 321 B	CL HIGH SHOALS TO LINCOLN CO.	2	1.78	24	1230	3.40		1,200		2,316	50		142		30								
TOTAL FOR PROJ NO. 12CR.303695.1						1.78		1230	3.40	0	1,200	0	2,316	50		142		30								
GRAND TOTAL						30.06		1485	26.90	46,587	4,520	2,450	42,791	809		2,726	26	1,550	18,200	8	24	2	83		29	