

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200889

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	303000000-E	862	425	LF	STEEL BM GUARDRAIL	588200000-N	SP	2	EA	GENERIC UTILITY ITEM FORCE MAIN LOCATOR WIRE BOX
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+67.00)	304500000-E	862	62.5	LF	STEEL BM GUARDRAIL, SHOP CURVED	588800000-E	SP	476	LF	GENERIC UTILITY ITEM 8" HDPE FORCE MAIN SEWER PIPE, DR 9, 200# WP
004300000-N	226	Lump Sum		GRADING	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	600000000-E	1605	1,025	LF	TEMPORARY SILT FENCE
005700000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING	319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
005700000-E	226	200	CY	UNDERCUT EXCAVATION	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	600900000-E	1610	110	TON	STONE FOR EROSION CONTROL, CLASS B
019500000-E	265	400	CY	SELECT GRANULAR MATERIAL	327000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	601200000-E	1610	130	TON	SEDIMENT CONTROL STONE
019600000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION	362800000-E	876	22	TON	PLAIN RIP RAP, CLASS I	601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
031800000-E	300	41	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	364900000-E	876	4	TON	PLAIN RIP RAP, CLASS B	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
036600000-E	310	220	LF	15" RC PIPE CULVERTS, CLASS III	365600000-E	876	243	SY	FILTER FABRIC FOR DRAINAGE	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
054600000-E	310	36	LF	*** CAA PIPE CULVERTS, ***** THICK (15", 0.064")	441200000-E	SP	199	SF	WORK ZONE SIGNS (STATIONARY)	602400000-E	1622	10	LF	TEMPORARY SLOPE DRAINS
054600000-E	310	128	LF	*** CAA PIPE CULVERTS, ***** THICK (48", 0.064")	441210000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
054600000-E	310	4	EA	*** CAA PIPE ELBOWS, ***** THICK (15", 0.064")	441220000-E	SP	20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	602900000-E	SP	960	LF	SAFETY FENCE
099500000-E	340	67	LF	PIPE REMOVAL	442000000-N	1120	5	EA	CHANGEABLE MESSAGE SIGNS	603000000-E	1630	140	CY	SILT EXCAVATION
122000000-E	545	50	TON	INCIDENTAL STONE BASE	443500000-N	1135	50	EA	CONES	603600000-E	1631	900	SY	MATTING FOR EROSION CONTROL
148900000-E	610	260	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	444610000-E	SP	60	LF	BARRICADES (TYPE III)	603800000-E	SP	85	SY	PERMANENT SOIL REINFORCEMENT MAT
149800000-E	610	340	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	445000000-N	1150	80	HR	FLAGGER	604200000-E	1632	500	LF	1/4" HARDWARE CLOTH
151900000-E	610	500	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	481000000-E	1205	7,448	LF	PAINT PAVEMENT MARKING LINES (4")	608400000-E	1660	1.5	ACR	SEEDING & MULCHING
156000000-E	620	60	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	490000000-N	1252	20	EA	PERMANENT RAISED PAVEMENT MARKERS	608700000-E	1660	1	ACR	MOWING
169300000-E	654	115	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	530000000-E	1505	16	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
228600000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES	530600000-E	SP	16	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
236700000-N	840	6	EA	FRAME WITH TWO GRATES, STD 840.29	531800000-E	1505	11	TON	PAVEMENT REPAIR FOR UTILITY WORK	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
255600000-E	846	280	LF	SHOULDER BERM GUTTER	570800000-E	1520	309	LF	*** PVC FORCE MAIN SEWER PIPE, ***** (6", SDR 21)	610800000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
					575600000-E	1520	725	LB	DUCTILE IRON SEWER PIPE FIT- TINGS, ***** (250# MIN WP)	611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
										611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
										613500000-E	SP	0.3	ACR	GENERIC EROSION CONTROL ITEM WETLAND GRASS PLANTING

5/28/99

17-MAR-2004 13:07
C:\project\13496.sum
RWB:annan AT