

County: Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	20,800 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+85.00)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	8,400 CY		
0008	0106000000-E	230	BORROW EXCAVATION	32,201 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	95 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,800 SY		
0011	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	228 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0014	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	600 SF		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	298 TON		
0016	0343000000-E	310	15" SIDE DRAIN PIPE	932 LF		
0017	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0018	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	248	LF	
0020	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	572	LF	
0021	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	272	LF	
0022	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	232	LF	
0023	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	192	LF	
0024	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	192	LF	
0025	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	72	LF	
0026	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	12	LF	
0027	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4	EA	
0028	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2	EA	
0029	0995000000-E	340	PIPE REMOVAL	1,674	LF	
0030	0996000000-N	350	PIPE CLEAN-OUT	10	EA	
0031	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0032	1220000000-E	545	INCIDENTAL STONE BASE	1,000	TON	
0033	1245000000-E	SP	SHOULDER RECONSTRUCTION	1	SMI	
0034	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,260	TON	
0035	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,182	TON	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,652 TON		
0037	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	686 TON		
0038	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	244 TON		
0039	1704000000-E	SP	PATCHING EXISTING PAVEMENT	500 TON		
0040	2209000000-E	838	ENDWALLS	20 CY		
0041	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0042	2319000000-N	840	FRAME WITH GRATE, DETAIL 840.***** (840.16)	2 EA		
0043	2330000000-N	840	FRAME WITH TWO GRATES, DETAIL 840.***** (840.29)	3 EA		
0044	2354000000-N	840	FRAME WITH GRATE, STD 840.22	2 EA		
0045	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.22)	2 EA		
0046	2556000000-E	846	SHOULDER BERM GUTTER	325 LF		
0047	2612000000-E	848	6" CONCRETE DRIVEWAY	200 SY		
0048	2619000000-E	850	4" CONCRETE PAVED DITCH	12 SY		
0049	3030000000-E	862	STEEL BM GUARDRAIL	350 LF		
0050	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0051	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	1 EA		
0054	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	23 LF		
0055	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	7 EA		
0056	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	36 LF		
0057	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	3 EA		
0058	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	3 EA		
0059	3564000000-E	866	SINGLE GATES, **** HIGH, *** WIDE, *** OPENING (4' HIGH, 10' WIDE, 10' OPEN- ING)	1 EA		
0060	3628000000-E	876	PLAIN RIP RAP, CLASS I	36 TON		
0061	3649000000-E	876	PLAIN RIP RAP, CLASS B	119 TON		
0062	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,083 SY		
0063	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0064	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	78 SF		
0065	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	328 SF		
0066	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	38 SF		
0067	4425000000-N	1125	WARNING FLAG SETS	3 EA		
0068	4430000000-N	1130	DRUMS	100 EA		
0069	4435000000-N	1135	CONES	50 EA		
0070	4446100000-E	SP	BARRICADES (TYPE III)	96 LF		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4450000000-N	1150	FLAGGER	720 HR		
0072	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0073	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0074	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	1 EA		
0075	4485000000-E	1170	PORTABLE CONCRETE BARRIER	230 LF		
0076	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	225 EA		
0077	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	24,000 LF		
0078	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	25,915 LF		
0079	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	100 LF		
0080	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	120 LF		
0081	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	12 EA		
0082	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	10 EA		
0083	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	99,830 LF		
0084	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	200 LF		
0085	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	240 LF		
0086	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24 EA		
0087	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20 EA		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,000	LF	
0089	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	225	EA	
0090	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	1,015	TON	
0091	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	1,015	TON	
0092	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)	78	LF	
0093	5450000000-E	1510	8" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)	8,235	LF	
0094	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	1,960	LB	
0095	5492000000-E	SP	3/4" PE WATER TUBING, SDR 9, *****WP (200# WP)	1,720	LF	
0096	5510000000-E	1510	3/4" CORPORATION STOP	39	EA	
0097	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	3	EA	
0098	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200# WP)	3	EA	
0099	5582000000-E	1510	***X*** TAPPING SADDLE (8" X 3/4")	39	EA	
0100	5648000000-N	1510	RELOCATE EXISTING WATER METER	45	EA	
0101	5666000000-E	1510	FIRE HYDRANT, *****# WP (150 #WP)	2	EA	
0102	6000000000-E	1605	TEMPORARY SILT FENCE	1,250	LF	
0103	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	940 TON		
0105	6012000000-E	1610	SEDIMENT CONTROL STONE	355 TON		
0106	6015000000-E	1615	TEMPORARY MULCHING	21.5 ACR		
0107	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	800 LB		
0108	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.25 TON		
0109	6024000000-E	1622	TEMPORARY SLOPE DRAINS	120 LF		
0110	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0111	6029000000-E	SP	SAFETY FENCE	450 LF		
0112	6030000000-E	1630	SILT EXCAVATION	2,550 CY		
0113	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,150 SY		
0114	6042000000-E	1632	1/4" HARDWARE CLOTH	140 LF		
0115	6045000000-E	SP	*** TEMPORARY PIPE (18")	40 LF		
0116	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	30 SY		
0117	6084000000-E	1660	SEEDING & MULCHING	24.5 ACR		
0118	6087000000-E	1660	MOWING	13 ACR		
0119	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0120	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0121	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500 LB		
0122	6108000000-E	1665	FERTILIZER TOPDRESSING	18.25 TON		
0123	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		

County : Onslow

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	16 EA		
0125	6123000000-E	1670	REFORESTATION	1 ACR		
<b>STRUCTURE ITEMS</b>						
0126	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+84.47 -L-)	Lump Sum	L.S.	
0127	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	73.2 CY		
0128	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+84.47 -L-)	Lump Sum	L.S.	
0129	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,298 LB		
0130	8364000000-E	450	HP12X53 STEEL PILES	420 LF		
0131	8386000000-E	450	PP 18 X 0.50 STEEL PILES	840 LF		
0132	8475000000-E	460	TWO BAR METAL RAIL	382.63 LF		
0133	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-8 1/2")	397.63 LF		
0134	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	235 TON		
0135	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	262 SY		
0136	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0137	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,379.75 LF		



C201182 (B-3682 W-3413)  
COUNTY: ONSLOW

2/16/99

Contract No: C201182  
County: Onslow

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General