

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201430

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	445000000-N	1150	100	MD	FLAGGER					
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	451000000-N	SP	24	HR	POLICE	602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.5)	465000000-N	1251	41	EA	TEMPORARY RAISED PAVEMENT MARKERS	602900000-E	SP	350	LF	SAFETY FENCE
004300000-N	226	Lump Sum		GRADING	468600000-E	1205	2,984	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	603000000-E	1630	85	CY	SILT EXCAVATION
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	469700000-E	1205	145	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	603600000-E	1631	785	SY	MATTING FOR EROSION CONTROL
005700000-E	226	200	CY	UNDERCUT EXCAVATION	471000000-E	1205	44	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	604200000-E	1632	220	LF	1/4" HARDWARE CLOTH
025500000-E	SP	40	TON	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	472500000-E	1205	16	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	608400000-E	1660	1.5	ACR	SEEDING & MULCHING
031800000-E	300	65	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	481000000-E	1205	5,966	LF	PAINT PAVEMENT MARKING LINES (4")	608700000-E	1660	1	ACR	MOWING
036000000-E	310	44	LF	12" RC PIPE CULVERTS, CLASS III	482000000-E	1205	290	LF	PAINT PAVEMENT MARKING LINES (8")	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
036600000-E	310	284	LF	15" RC PIPE CULVERTS, CLASS III	483500000-E	1205	88	LF	PAINT PAVEMENT MARKING LINES (24")	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
037200000-E	310	160	LF	18" RC PIPE CULVERTS, CLASS III	484500000-N	1205	32	EA	PAINT PAVEMENT MARKING SYMBOL	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
039600000-E	310	72	LF	42" RC PIPE CULVERTS, CLASS III	490000000-N	1252	41	EA	PERMANENT RAISED PAVEMENT MARKERS	610800000-E	1665	1	TON	FERTILIZER TOPDRESSING
071400000-E	310	44	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	530000000-E	1505	68.1	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
099500000-E	340	60	LF	PIPE REMOVAL	530600000-E	SP	68.1	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
122000000-E	545	200	TON	INCIDENTAL STONE BASE	554000000-E	1510	1	EA	6" GATE VALVE & VALVE BOX, 200# WP	706000000-E	1705	475	LF	SIGNAL CABLE
148900000-E	610	933	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	556400000-E	SP	1	EA	*** BUTTERFLY VALVE & VALVE BOX (16")	712000000-E	1705	2	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
149800000-E	610	858	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	566600000-E	1510	1	EA	FIRE HYDRANT, ***** WP (150 # WP)	714400000-E	1705	4	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
151900000-E	610	955	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	577500000-E	1525	1	EA	4" DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH	726400000-E	1710	295	LF	MESSENGER CABLE (3/8")
156000000-E	620	138	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	578000000-E	1525	4	LF	PRECAST CONC MANHOLE WALL, * DIA, OVER 6' HT (4" DIA, OVER 6' HT)	728800000-E	1715	25	LF	TRENCHING (PAVED)
169300000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	579800000-E	1530	399	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", TC SEWER)	730000000-E	1715	130	LF	TRENCHING (UNPAVED)
227500000-E	SP	14	CY	FLOWABLE FILL	581000000-E	1530	478	LF	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER)	732400000-N	1716	6	EA	JUNCTION BOX (STANDARD SIZE)
228600000-N	840	17	EA	MASONRY DRAINAGE STRUCTURES	582000000-N	SP	1	EA	GENERIC UTILITY ITEM 4" DIA PRECAST CONC SEWER MANHOLE, 0-6' DEPTH WITH WATERTIGHT RING & COVER	736000000-N	1720	2	EA	WOOD POLE
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	582000000-N	SP	1	EA	GENERIC UTILITY ITEM INSTALL 4" WATER METER & VAULT	737200000-N	1721	4	EA	GUY ASSEMBLY
237400000-N	840	5	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	588200000-N	SP	1	EA	GENERIC UTILITY ITEM REMOVE & STOCKPILE EXT FIRE HYDRANT	740800000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
237400000-N	840	4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	588200000-N	SP	1	EA	GENERIC UTILITY ITEM 16" DI WATER PIPE, PC 350	742000000-E	1722	2	EA	2" RISER WITH WEATHERHEAD
237400000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	588800000-E	SP	493.3	LF	GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350	744400000-E	1725	1,755	LF	INDUCTIVE LOOP SAWCUT
239600000-N	840	4	EA	FRAME WITH COVER, STD 840.54	588800000-E	SP	10	LF	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT SEWER PIPE, CLASS 50	745600000-E	1726	1,180	LF	LEAD-IN CABLE
247300000-N	SP	2	EA	GENERIC DRAINAGE ITEM FLAP GATE	589400000-E	SP	4	CY	GENERIC UTILITY ITEM CONCRETE FOR PIERS, CLASS A	763600000-N	1745	5	EA	SIGN FOR SIGNALS
253500000-E	846	540	LF	***X*** CONCRETE CURB (9" X 12")	591200000-N	SP	Lump Sum		GENERIC UTILITY ITEM INSTALL 6" GAS MAIN	785200000-N	SP	1	EA	DETECTOR CARD (NEMA TS-2)
254900000-E	846	1,630	LF	2-6" CONCRETE CURB & GUTTER	600000000-E	1605	1,550	LF	TEMPORARY SILT FENCE					
259100000-E	848	645	SY	4" CONCRETE SIDEWALK	600600000-E	1610	50	TON	STONE FOR EROSION CONTROL, CLASS A					
259800000-E	848	41	SY	CONCRETE WHEELCHAIR RAMPS	600900000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS B					
261200000-E	848	286	SY	6" CONCRETE DRIVEWAY	601200000-E	1610	65	TON	SEDIMENT CONTROL STONE					
283000000-N	858	10	EA	ADJUSTMENT OF MANHOLES	601500000-E	1615	1.5	ACR	TEMPORARY MULCHING					
284500000-N	858	5	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
364900000-E	876	3	TON	PLAIN RIP RAP, CLASS B	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING					
365600000-E	876	160	SY	FILTER FABRIC FOR DRAINAGE	602400000-E	1622	35	LF	TEMPORARY SLOPE DRAINS					
398200000-N	SP	Lump Sum		GENERIC WALL ITEM PILE/PANEL RETAINING WALL										
441200000-E	SP	73	SF	WORK ZONE SIGNS (STATIONARY)										
441210000-E	SP	100	SF	WORK ZONE SIGNS (PORTABLE)										
441220000-E	SP	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)										
441500000-N	1115	1	EA	FLASHING ARROW PANELS, TYPE C										
442000000-N	1120	5	EA	CHANGEABLE MESSAGE SIGNS										
442500000-N	1125	2	EA	WARNING FLAG SETS										
443000000-N	1130	260	EA	DRUMS										
443500000-N	1135	260	EA	CONES										
444610000-E	SP	80	LF	BARRICADES (TYPE III)										