STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
B-3685	X-1

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	7	1
10+50.00	18	5
11+00.00	8	12
11+50.00	18	8
12+00.00	20	5
12+50.00	12	10
13+00.00	15	11
13+50.00	20	12
14+00.00	19	15
14+50.00	16	18
15+00.00	17	17
15+50.00	21	13
16+00.00	25	13
16+50.00	27	21

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+00.00	1	1
18+50.00	29	23
19+00.00	25	17
19+50.00	20	15
20+00.00	11	15

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	26	0
10+50.00	61	0
11+00.00	20	0
11+50.00	28	0
12+00.00	48	0
12+50.00	64	0
13+00.00	41	0
13+50.00	23	0
14+00.00	25	1
14+50.00	15	4
15+00.00	13	5
15+50.00	19	4
16+00.00	21	6
16+50.00	21	10

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+00.00	1	3
18+50.00	28	68
19+00.00	20	14
19+50.00	41	5
20+00.00	39	0

CROSS SECTION INDEX SHEET

LINE	STATION TO STATION		SHEET TO SHEET	
-L-	10+00.00	20+00.00	X-2	X-4