

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.5) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 000E | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 000E | 0057000000-E | 226 | UNDERCUT EXCAVATION | 200 CY | | |
| 0007 | 0255000000-E | SP | GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL | 40 TON | | |
| 000E | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 65 TON | | |
| 000E | 0360000000-E | 310 | 12" RC PIPE CULVERTS, CLASS III | 44 LF | | |
| 001C | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 284 LF | | |
| 0011 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 160 LF | | |
| 0012 | 0396000000-E | 310 | 42" RC PIPE CULVERTS, CLASS III | 72 LF | | |
| 0013 | 0714000000-E | 310 | 18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 44 LF | | |
| 0014 | 0995000000-E | 340 | PIPE REMOVAL | 60 LF | | |
| 001E | 1220000000-E | 545 | INCIDENTAL STONE BASE | 200 TON | | |
| 001E | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 933 TON | | |
| 0017 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 858 TON | | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 001E | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 955 TON | | |
| 001E | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 138 TON | | |
| 002C | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 20 TON | | |
| 0021 | 2275000000-E | SP | FLOWABLE FILL | 14 CY | | |
| 0022 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 17 EA | | |
| 002E | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0024 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E) | 5 EA | | |
| 002E | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F) | 4 EA | | |
| 002E | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 2 EA | | |
| 0027 | 2396000000-N | 840 | FRAME WITH COVER, STD 840.54 | 4 EA | | |
| 002E | 2473000000-N | SP | GENERIC DRAINAGE ITEM FLAP GATE | 2 EA | | |
| 002E | 2535000000-E | 846 | ***X*** CONCRETE CURB (9" X 12") | 540 LF | | |
| 003C | 2549000000-E | 846 | 2'-6" CONCRETE CURB & GUTTER | 1,630 LF | | |
| 0031 | 2591000000-E | 848 | 4" CONCRETE SIDEWALK | 645 SY | | |
| 0032 | 2598000000-E | 848 | CONCRETE WHEELCHAIR RAMPS | 41 SY | | |
| 003E | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 286 SY | | |
| 0034 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 10 EA | | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 003E | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 5 EA | | |
| 003E | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 3 TON | | |
| 0037 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 160 SY | | |
| 003E | 3982000000-N | SP | GENERIC WALL ITEM PILE/PANEL RETAINING WALL | Lump Sum | L.S. | |
| 003E | 4412000000-E | SP | WORK ZONE SIGNS (STATIONARY) | 73 SF | | |
| 004C | 4412100000-E | SP | WORK ZONE SIGNS (PORTABLE) | 100 SF | | |
| 0041 | 4412200000-E | SP | WORK ZONE SIGNS (BARRICADE MOUNTED) | 57 SF | | |
| 0042 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 1 EA | | |
| 004E | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGNS | 5 EA | | |
| 0044 | 4425000000-N | 1125 | WARNING FLAG SETS | 2 EA | | |
| 004E | 4430000000-N | 1130 | DRUMS | 260 EA | | |
| 004E | 4435000000-N | 1135 | CONES | 260 EA | | |
| 0047 | 4446100000-E | SP | BARRICADES (TYPE III) | 80 LF | | |
| 004E | 4455000000-N | 1150 | FLAGGER | 100 MD | | |
| 004E | 4510000000-N | SP | POLICE | 24 HR | | |
| 005C | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 41 EA | | |
| 0051 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 2,984 LF | | |
| 0052 | 4697000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) | 145 LF | | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0053 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 44 | LF | |
| 0054 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 16 | EA | |
| 0055 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 5,966 | LF | |
| 0056 | 4820000000-E | 1205 | PAINT PAVEMENT MARKING LINES (8") | 290 | LF | |
| 0057 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 88 | LF | |
| 0058 | 4845000000-N | 1205 | PAINT PAVEMENT MARKING SYMBOL | 32 | EA | |
| 0059 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 41 | EA | |
| 0060 | 5300000000-E | 1505 | FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI) | 68.1 | TON | |
| 0061 | 5306000000-E | SP | BEDDING MATERIAL, UTILITIES CLASS ***** (IV) | 68.1 | TON | |
| 0062 | 5540000000-E | 1510 | 6" GATE VALVE & VALVE BOX, 200# WP | 1 | EA | |
| 0063 | 5564000000-E | SP | *** BUTTERFLY VALVE & VALVE BOX (16") | 1 | EA | |
| 0064 | 5666000000-E | 1510 | FIRE HYDRANT, *****# WP (150 # WP) | 1 | EA | |
| 0065 | 5775000000-E | 1525 | 4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH | 1 | EA | |
| 0066 | 5780000000-E | 1525 | PRECAST CONC MANHOLE WALL, *' DIA, OVER 6' HT (4' DIA, OVER 6' HT) | 4 | LF | |
| 0067 | 5798000000-E | 1530 | FILL OR REMOVE ABANDONED *** PIPE, ***** (8", TC SEWER) | 399 | LF | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 006E | 5810000000-E | 1530 | FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER) | 478 LF | | |
| 006E | 5882000000-N | SP | GENERIC UTILITY ITEM 4' DIA PRECAST CONC SEWER MAN-HOLE, 0-6' DEPTH WITH WATERTIGHT RING & COVER | 1 EA | | |
| 007C | 5882000000-N | SP | GENERIC UTILITY ITEM INSTALL 4" WATER METER & VAULT | 1 EA | | |
| 0071 | 5882000000-N | SP | GENERIC UTILITY ITEM REMOVE & STOCKPILE EXT FIRE HYDRANT | 1 EA | | |
| 0072 | 5888000000-E | SP | GENERIC UTILITY ITEM 16" DI WATER PIPE, PC 350 | 493.3 LF | | |
| 0073 | 5888000000-E | SP | GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350 | 10 LF | | |
| 0074 | 5888000000-E | SP | GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT SEWER PIPE, CLASS 50 | 279.4 LF | | |
| 007E | 5888000000-E | SP | GENERIC UTILITY ITEM 8" DI SEWER PIPE, CLASS 50 | 154.25 LF | | |
| 007E | 5888000000-E | SP | GENERIC UTILITY ITEM 8" DI WATER PIPE, PC 350 | 357.05 LF | | |
| 0077 | 5894000000-E | SP | GENERIC UTILITY ITEM CONCRETE FOR PIERS, CLASS A | 4 CY | | |
| 007E | 5906000000-E | SP | GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP | 2,405 LB | | |
| 007E | 5912000000-N | SP | GENERIC UTILITY ITEM INSTALL 6" GAS MAIN | Lump Sum | L.S. | |
| 008C | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,550 LF | | |
| 0081 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 50 TON | | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0082 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 75 | TON | |
| 0083 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 65 | TON | |
| 0084 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1.5 | ACR | |
| 0085 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 | LB | |
| 0086 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.25 | TON | |
| 0087 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 35 | LF | |
| 0088 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 1 | EA | |
| 0089 | 6029000000-E | SP | SAFETY FENCE | 350 | LF | |
| 009C | 6030000000-E | 1630 | SILT EXCAVATION | 85 | CY | |
| 0091 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 785 | SY | |
| 0092 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 220 | LF | |
| 0093 | 6084000000-E | 1660 | SEEDING & MULCHING | 1.5 | ACR | |
| 0094 | 6087000000-E | 1660 | MOWING | 1 | ACR | |
| 009E | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 | LB | |
| 0096 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 | TON | |
| 0097 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 | LB | |
| 009E | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1 | TON | |
| 0099 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 1 | HR | |
| 010C | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 8 | EA | |
| 0101 | 7060000000-E | 1705 | SIGNAL CABLE | 475 | LF | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--------------------------------------|-------------|-----------|--------|
| 0102 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 2 EA | | |
| 0103 | 7144000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 5 SECTION) | 4 EA | | |
| 0104 | 7264000000-E | 1710 | MESSENGER CABLE (3/8") | 295 LF | | |
| 0105 | 7288000000-E | 1715 | TRENCHING (PAVED) | 25 LF | | |
| 0106 | 7300000000-E | 1715 | TRENCHING (UNPAVED) | 130 LF | | |
| 0107 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 6 EA | | |
| 0108 | 7360000000-N | 1720 | WOOD POLE | 2 EA | | |
| 0109 | 7372000000-N | 1721 | GUY ASSEMBLY | 4 EA | | |
| 0110 | 7408000000-E | 1722 | 1" RISER WITH WEATHERHEAD | 1 EA | | |
| 0111 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 2 EA | | |
| 0112 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 1,755 LF | | |
| 0113 | 7456000000-E | 1726 | LEAD-IN CABLE | 1,180 LF | | |
| 0114 | 7636000000-N | 1745 | SIGN FOR SIGNALS | 5 EA | | |
| 0115 | 7852000000-N | SP | DETECTOR CARD (NEMA TS-2) | 1 EA | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|--|-----------|------|--|
| 0116 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+47.50 -L-) | Lump Sum | L.S. | |
| 0117 | 8121000000-N | SP | UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+47.50 -L-) | Lump Sum | L.S. | |
| 0118 | 8364000000-E | 450 | HP12X53 STEEL PILES | 495 LF | | |

County : Pitt

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--|--------------|-------|---|------------|-----------|--------|
| 0119 | 8384000000-E | 450 | HP14X73 STEEL PILES | 600 LF | | |
| 0120 | 8406000000-N | SP | GALVANIZING STEEL PILES AT STA ***** (17 + 47.50 -L-) | Lump Sum | L.S. | |
| 0121 | 8608000000-E | 876 | PLAIN RIP RAP CLASS II (2'-0" THICK) | 305 TON | | |
| 0122 | 8765000000-N | SP | CONSTRUCTION OF SUBSTRUCTURE | Lump Sum | L.S. | |
| 0123 | 8766000000-N | SP | CONSTRUCTION OF SUPERSTRUCTURE | Lump Sum | L.S. | |
| 1441/Feb01/Q31458.7/D578442900000/E123 | | | Total Amount Of Bid For Entire Project : | | | |

C201430 (B-3685)
COUNTY: PITT

2/16/99

Contract No: C201430
County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General