

PROJECT NO.	SHEET NO.	TOTAL NO.
8CR.20831.3, 8CR.308321.3	2	4

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0C TONS	SURFACE COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TON	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	CONCRETE WHEELCHAIR RAMPS EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA
8CR.20831.3	Scotland	1	SR 1614	FROM SR 1615 TO NCL OF LAURINBURG	2	1	22	50		200			765	50				
		2	SR 1614	FROM US 15-401 TO CONST. JT.	2	1.59	22	80		200			1,265	83				
		3	SR 1105	FROM SR 1300 TO NCL OF LAURINBURG	2	1.63	22	85		200			1,260	82				
TOTAL FOR PROJ NO. 8CR.20831.3						4.22		215		600		3,290	215					
8CR.308321.3	Scotland	4	SR 1614	FROM CONST. JT. TO NCL OF LAURINBURG	2	0.32	22	25		200			275	18				
		5	SR 1105	FROM US 74 BUS. TO NCL OF LAURINBURG	2	0.3	22	25		200			230	15				
		6	SR 1105	FROM SR 1116 TO US 74 BUS.	4	0.86	22	100	520	200	635	1005		27	60			
		7	SR 1105	FROM CONST. JT. TO SR 1116	1	1.34	22	70		200		1605			96			
		8	SR 1107	FROM US 401 BUS. TO US 401 BUS.	1,3	2.57	33.5	50		200		4320		259	62	34	24	
TOTAL FOR PROJ NO. 8CR.308321.3						5.39		270	520	1000	635	6930	505	60	415	62	34	24
GRAND TOTAL						9.61		485	520	1600	635	6930	3,795	275	415	62	34	24