STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PLAN FOR PROPOSED
TRAFFIC CONTROL, MARKING & DELINEATION

ROBESON COUNTY

B-4248

TIP PROJECT:

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-
ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C.,
DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE
CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1110.01	STATIONARY WORK ZONE SIGNS
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS (PERMANENT)

INDEX OF SHEETS

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, INDEX OF SHEETS AND FINAL PAVEMENT MARKING SCHEDULE
TCP-2	GENERAL NOTES AND PHASING
TCP-3	DETOUR SIGNING
TCP-4	REPLACEMENT DETAIL FOR RSD 1101.04
TCP-5	REPLACEMENT DETAIL FOR RSD 1145.01

LEGEND

GENERAL

- ← DIRECTION OF TRAFFIC FLOW
- NORTH ARROW
- —— PROPOSED PVMT. ------- EXIST. PVMT.
- WORK AREA
- REMOVAL OF EXISTING PAVEMENT

TRAFFIC CONTROL DEVICES

- I TYPE I BARRICADE
- II TYPE II BARRICADE
- TYPE III BARRICADE
- ▲ CONE
- ● DRUM
- FLASHING ARROW PANEL (TYPE C)
- TYPE 'B' WARNING LIGHT
- STATIONARY SIGN
- PORTABLE SIGN
- STATIONARY OR PORTABLE SIGN
- WARNING FLAGS
- CRASH CUSHION
- CHANGEABLE MESSAGE SIGN
- TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
- POLICE
- FLAGGER

PAVEMENT MARKINGS

- ☐ CRYSTAL/CRYSTAL PAVEMENT MARKER
- ◆ YELLOW/YELLOW PAVEMENT MARKER
- ▮ CRYSTAL/RED PAVEMENT MARKER
- ↑↖◁ PAVEMENT MARKING SYMBOLS

Final Pavement Marking Schedule

TIP Project # B-4248

SYMBOL	DESCRIPTION	PAY ITEM QUANITY BREAKDOWN		TOTAL QUANTITY	
	FINAL PAVEMENT MARKINGS				
	PAINT (4")				
PA	WHITE EDGELINE (2X)	4800	LF		
PI	YELLOW DOUBLE CENTER (2X)	4800	LF		
			TOTAL	9600	LF
	MARKERS				
	PERMANENT RAISED PAVEMENT MARKERS				
MA	YELLOW & YELLOW	20	EA		
			TOTAL	20	EA

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, 1X IMPLIES A SINGLE APPLICATION, 2X IMPLIES TWO
APPLICATIONS, AND 3X IMPLIES THREE APPLICATIONS.

APPROVED: Joseph Ishak
DATE: 12/3/04

SEAL
NORTH CAROLINA
PROFESSIONAL
SEAL
028380
ENGINEER
JOSEPH ISHAK

PLAN PREPARED BY: N.C.D.O.T. TRAFFIC CONTROL, MARKING &
DELINEATION UNIT

J.S. BOURNE, PE — TRAFFIC CONTROL ENGINEER

JOSEPH ISHAK, PE — TRAFFIC CONTROL PROJECT ENGINEER

BETSY L. WATSON, PE — TRAFFIC CONTROL PROJECT DESIGN ENGINEER

JOE FUTRELL — TRAFFIC CONTROL DESIGN ENGINEER