

EB1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-20	13' LT	16+48	4.2-5.7	A-4(2)	30	8	7.1	47.9	16.8	28.3	100	97	55	-	-
SS-21	13' LT	16+48	9.2-10.7	A-6(5)	34	12	10.5	41.6	19.6	28.3	99	93	57	-	-

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-14	21' RT	16+43	3.7-5.2	A-6(5)	39	11	21.2	30.1	24.4	24.2	98	84	57	-	-

B1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-18	25' LT	17+10	5.2-6.0	A-2-4(0)	37	NP	28.1	48.9	17.0	6.1	93	80	31	-	-
SS-19	25' LT	17+10	19.5-21.0	A-4(0)	27	NP	25.1	38.8	26.1	10.1	99	86	46	-	-

B1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-15	24' RT	17+01	6.9-8.4	A-1-a(0)	29	NP	63.8	23.2	8.9	4.0	42	20	7	-	-
SS-16	24' RT	17+01	12.8-13.4	A-2-4(0)	33	NP	37.2	40.8	18.0	4.0	95	74	29	-	-
SS-17	24' RT	17+01	14.4-15.9	A-4(0)	33	NP	30.3	41.4	22.2	6.1	100	83	40	-	-

B2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-6	19' LT	17+83	9.0-10.5	A-2-4(0)	26	NP	10.7	64.6	12.5	12.2	100	98	33	-	-
SS-7	19' LT	17+83	14.0-15.5	A-2-4(0)	33	NP	23.9	48.8	23.2	4.1	72	61	29	-	-
SS-8	19' LT	17+83	19.0-20.5	A-4(0)	37	NP	11.6	48.8	31.5	8.1	100	95	54	-	-
SS-9	19' LT	17+83	24.0-25.5	A-2-4(0)	32	NP	47.2	32.4	16.3	4.1	80	52	22	-	-

B2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-12	30' RT	17+83	4.0-5.5	A-4(0)	24	NP	16.4	53.7	11.7	18.2	100	96	37	-	-
SS-13	30' RT	17+83	14.0-15.5	A-5(0)	42	NP	17.4	52.3	22.2	8.1	95	87	43	-	-

EB2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	21' LT	18+16	3.9-5.4	A-6(3)	33	11	7.3	48.2	14.1	30.4	100	98	53	-	-
SS-2	21' LT	18+16	8.9-9.4	A-2-4(0)	25	NP	13.8	69.3	8.8	8.1	100	99	24	-	-
SS-3	21' LT	18+16	13.9-15.4	A-2-4(0)	34	NP	35.7	38.5	19.8	6.1	93	71	34	-	-
SS-4	21' LT	18+16	18.9-20.4	A-4(0)	37	NP	17.2	51.3	25.4	6.1	100	92	45	-	-
SS-5	21' LT	18+16	28.9-29.4	A-2-4(0)	29	NP	48.0	27.8	16.1	8.1	84	54	25	-	-

EB2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-10	21' RT	18+04	14.2-15.7	A-2-4(0)	30	NP	41.5	34.7	17.7	6.1	90	65	28	-	-
SS-11	21' RT	18+04	34.2-35.7	A-5(0)	47	NP	20.3	43.4	28.3	8.1	90	78	43	-	-