

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201183																				
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	
0000100000-N	800	Lump Sum		MOBILIZATION	2286000000-N	840	7	EA	MASONRY DRAINAGE STRUCTURES	4475000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	6123000000-E	1670	0.5	ACR	REFORESTATION	
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+30.00)	2354200000-N	840	2	EA	FRAME WITH GRATE, STD 840.24	4650000000-N	1251	40	EA	TEMPORARY RAISED PAVEMENT MARKERS						
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	2355000000-N	840	4	EA	FRAME WITH GRATE, STD 840.29	4810000000-E	1205	25,600	LF	PAINT PAVEMENT MARKING LINES (4")						
0057000000-E	226	350	CY	UNDERCUT EXCAVATION	3030000000-E	862	950	LF	STEEL BM GUARDRAIL	4900000000-N	1252	20	EA	PERMANENT RAISED PAVEMENT MARKERS						
0063000000-N	SP	Lump Sum		GRADING	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6000000000-E	1605	700	LF	TEMPORARY SILT FENCE						
0080000000-E	SP	100	TON	CLASS IV SUBGRADE STABILIZATION	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A						
0106000000-E	230	13,000	CY	BORROW EXCAVATION	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6009000000-E	1610	350	TON	STONE FOR EROSION CONTROL, CLASS B						
0134000000-E	240	662	CY	DRAINAGE DITCH EXCAVATION	3317000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77	6012000000-E	1610	320	TON	SEDIMENT CONTROL STONE						
0195000000-E	265	250	CY	SELECT GRANULAR MATERIAL	3360000000-E	863	297	LF	REMOVE EXISTING GUARDRAIL	6015000000-E	1615	4.5	ACR	TEMPORARY MULCHING						
0196000000-E	270	250	SY	FABRIC FOR SOIL STABILIZATION	3649000000-E	876	260	TON	PLAIN RIP RAP, CLASS B	6018000000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING						
0318000000-E	300	72	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3656000000-E	876	1,400	SY	FILTER FABRIC FOR DRAINAGE	6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING						
0366000000-E	310	60	LF	15" RC PIPE CULVERTS, CLASS III	3659000000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6024000000-E	1622	170	LF	TEMPORARY SLOPE DRAINS						
0372000000-E	310	432	LF	18" RC PIPE CULVERTS, CLASS III	3982000000-N	SP	Lump Sum		GENERIC WALL ITEM SOIL NAIL RETAINING WALL, STA. 12+30 -L- TO 14+30 -L-	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS						
0378000000-E	310	36	LF	24" RC PIPE CULVERTS, CLASS III	4025000000-E	901	12.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6029000000-E	SP	300	LF	SAFETY FENCE						
0708000000-E	310	152	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4072000000-E	903	28	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	6030000000-E	1630	2,165	CY	SILT EXCAVATION						
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4102000000-N	904	2	EA	SIGN ERECTION, TYPE E	6036000000-E	1631	1,500	SY	MATTING FOR EROSION CONTROL						
1220000000-E	545	300	TON	INCIDENTAL STONE BASE	4155000000-N	907	14	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6042000000-E	1632	140	LF	1/4" HARDWARE CLOTH						
1489000000-E	610	648	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4412000000-E	SP	84	SF	WORK ZONE SIGNS (STATIONARY)	6070000000-N	SP	8	EA	SPECIAL STILLING BASINS						
1498000000-E	610	846	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	6084000000-E	1660	7.1	ACR	SEEDING & MULCHING						
1525000000-E	SP	962	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4412200000-E	SP	40	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6090000000-E	1660	3	ACR	MOWING						
1560000000-E	620	131	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4430000000-N	1130	32	EA	DRUMS	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING						
2000000000-N	806	16	EA	RIGHT OF WAY MARKERS	4435000000-N	1135	50	EA	CONES	6096000000-E	1662	125	LB	SEED FOR SUPPLEMENTAL SEEDING						
2253000000-E	840	1.2	CY	PIPE COLLARS	4446100000-E	SP	48	LF	BARRICADES (TYPE III)	6108000000-E	1665	3.75	TON	FERTILIZER TOPDRESSING						
					4450000000-N	1150	240	HR	FLAGGER	6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING						
										6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL						