

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+ 30.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	13,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	662 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	72 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	432 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	36 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	152 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	648 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	846 TON		
002C	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	962 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	131 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
0023	2253000000-E	840	PIPE COLLARS	1.2 CY		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0025	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0026	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	260 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	950 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	1 EA		
0033	3360000000-E	863	REMOVE EXISTING GUARDRAIL	297 LF		
0034	3649000000-E	876	PLAIN RIP RAP, CLASS B	260 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,400 SY		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0037	3982000000-N	SP	GENERIC WALL ITEM SOIL NAIL RETAINING WALL, STA . 12+30 -L- TO 14+30 -L-	Lump Sum	L.S.	
0038	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	12.5 SF		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	28 LF		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0041	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	14 EA		
0042	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	84 SF		
0043	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0044	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0045	4430000000-N	1130	DRUMS	32 EA		
0046	4435000000-N	1135	CONES	50 EA		
0047	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0048	4450000000-N	1150	FLAGGER	240 HR		
0049	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)	1 EA		
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40 EA		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	25,600 LF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	20 EA		
0053	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	320 TON		
0057	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0058	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0059	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
0060	6024000000-E	1622	TEMPORARY SLOPE DRAINS	170 LF		
0061	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0062	6029000000-E	SP	SAFETY FENCE	300 LF		
0063	6030000000-E	1630	SILT EXCAVATION	2,165 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	140 LF		
0066	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0067	6084000000-E	1660	SEEDING & MULCHING	7.1 ACR		
0068	6087000000-E	1660	MOWING	3 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0074	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0075	6123000000-E	1670	REFORESTATION	0.5 ACR		
STRUCTURE ITEMS						
0076	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+27.50 -L-)	Lump Sum	L.S.	
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+27.50 -L-)	Lump Sum	L.S.	
0078	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	153.6 LF		
0079	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	36 LF		
008C	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	114.8 LF		
0081	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0082	8116000000-E	SP	CSL TUBES	818 LF		
0083	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,044 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	8,060 SF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	138.4 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+27.50 -L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	37,021 LB		
0088	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	7,096 LB		
0089	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	960.35 LF		
009C	8364000000-E	450	HP12X53 STEEL PILES	440 LF		
0091	8503000000-E	460	CONCRETE BARRIER RAIL	325.76 LF		
0092	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	405 TON		
0093	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	450 SY		
0094	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0095	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0711/Feb10/Q117058.46/D430148520000/E95

Total Amount Of Bid For Entire Project :

C201183 (B-3694)
COUNTY: ROCKINGHAM

2/16/99

Contract No: C201183
County: Rockingham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General