

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201186

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+15.00)
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (28+52.50)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
1489000000-E	610	1,970	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1519000000-E	610	1,170	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	155	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2556000000-E	846	160	LF	SHOULDER BERM GUTTER
2570000000-N	SP	3	EA	MODIFIED CONCRETE FLUME
3030000000-E	862	1,575	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3649000000-E	876	11	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	515	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	288	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4446100000-E	SP	96	LF	BARRICADES (TYPE III)
4685000000-E	1205	3,062	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)

ItemNumber	Sec #	Quantity	Unit	Description
4686000000-E	1205	3,062	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4905000000-N	1253	19	EA	SNOWFLOWABLE PAVEMENT MARKERS
6000000000-E	1605	3,065	LF	TEMPORARY SILT FENCE
6006000000-E	1610	100	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	35	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	70	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	2,680	LF	SAFETY FENCE
6030000000-E	1630	40	CY	SILT EXCAVATION
6036000000-E	1631	1,985	SY	MATTING FOR EROSION CONTROL
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	4	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99