

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000950000-E	SP	GENERIC MISCELLANEOUS ITEM ROCK PLATING	2,200 SF		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	96,000 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+36.00 -L-)	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0008	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	150 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	134 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	896 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	100 LF		
0017	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	108 LF		
0018	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	4 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92 LF		
0020	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0021	0995000000-E	340	PIPE REMOVAL	30 LF		
0022	1121000000-E	520	AGGREGATE BASE COURSE	260 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0024	1330000000-E	607	INCIDENTAL MILLING	30 SY		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,290 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	640 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	780 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	133 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	55 TON		
0030	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	155 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	80 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	450 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0035	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0037	2220000000-E	838	REINFORCED ENDWALLS	2 CY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2264000000-E	840	PIPE PLUGS	0.35	CY	
0039	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	12	EA	
0040	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	20	LF	
0041	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
0042	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8	EA	
0043	2396000000-N	840	FRAME WITH COVER, STD 840.54	2	EA	
0044	2462000000-E	SP	*** SLUICE GATE (25")	2	EA	
0045	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS WASTE RETENTION BASIN	Lump Sum	L.S.	
0046	2556000000-E	846	SHOULDER BERM GUTTER	960	LF	
0047	3030000000-E	862	STEEL BM GUARDRAIL	662.5	LF	
0048	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75	LF	
0049	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0050	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4	EA	
0051	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0053	3360000000-E	863	REMOVE EXISTING GUARDRAIL	760	LF	
0054	3628000000-E	876	PLAIN RIP RAP, CLASS I	290	TON	
0055	3649000000-E	876	PLAIN RIP RAP, CLASS B	13	TON	
0056	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,270	SY	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	24	SF	
0058	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	79	SF	
0059	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	215	LF	
0060	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0061	4102000000-N	904	SIGN ERECTION, TYPE E	11	EA	
0062	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	18	EA	
0063	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	296	SF	
0064	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	170	SF	
0065	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	47	SF	
0066	4425000000-N	1125	WARNING FLAG SETS	2	EA	
0067	4430000000-N	1130	DRUMS	60	EA	
0068	4435000000-N	1135	CONES	60	EA	
0069	4446100000-E	SP	BARRICADES (TYPE III)	148	LF	
0070	4455000000-N	1150	FLAGGER	120	MD	
0071	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1	EA	
0072	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1	EA	
0073	4485000000-E	1170	PORTABLE CONCRETE BARRIER	40	LF	
0074	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARK- ING LINES (4")	520	LF	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	34 EA		
0076	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,904 LF		
0077	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	80 LF		
0078	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	5,704 LF		
0079	4847140000-E	SP	POLYUREA PAVEMENT MARKING LINES (24")	40 LF		
0080	4847220000-N	SP	POLYUREA PAVEMENT MARKING SYMBOL	5 EA		
0081	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	780 LF		
0082	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	33 EA		
0083	6000000000-E	1605	TEMPORARY SILT FENCE	950 LF		
0084	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0085	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	550 TON		
0086	6012000000-E	1610	SEDIMENT CONTROL STONE	490 TON		
0087	6015000000-E	1615	TEMPORARY MULCHING	8.5 ACR		
0088	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0089	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0090	6024000000-E	1622	TEMPORARY SLOPE DRAINS	115 LF		
0091	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0092	6029000000-E	SP	SAFETY FENCE	600 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6030000000-E	1630	SILT EXCAVATION	1,800 CY		
0094	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,405 SY		
0095	6042000000-E	1632	1/4" HARDWARE CLOTH	700 LF		
0096	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0097	6084000000-E	1660	SEEDING & MULCHING	14 ACR		
0098	6087000000-E	1660	MOWING	5 ACR		
0099	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0100	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0101	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0102	6108000000-E	1665	FERTILIZER TOPDRESSING	10.5 TON		
0103	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0104	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0105	6123000000-E	1670	REFORESTATION	0.2 ACR		
STRUCTURE ITEMS						
0106	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+36.00 -L-)	Lump Sum	L.S.	
0107	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+36.00 -L-)	Lump Sum	L.S.	
0108	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	48 LF		
0109	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	60 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8113000000-N	SP	SID INSPECTION	2 EA		
0111	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0112	8116000000-E	SP	CSL TUBES	472 LF		
0113	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+36.00 -L-)	Lump Sum	L.S.	
0114	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,178 SF		
0115	8161000000-E	420	GROOVING BRIDGE FLOORS	5,310 SF		
0116	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	94 CY		
0117	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+36.00 -L-)	Lump Sum	L.S.	
0118	8217000000-E	425	REINFORCING STEEL (BRIDGE)	21,891 LB		
0119	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,314 LB		
0120	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	641.5 LF		
0121	8364000000-E	450	HP12X53 STEEL PILES	195 LF		
0122	8391000000-N	450	STEEL PILE POINTS	13 EA		
0123	8503000000-E	460	CONCRETE BARRIER RAIL	219.19 LF		
0124	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	605 TON		
0125	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	670 SY		
0126	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0127	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

C201455 (B-3300)
COUNTY: ASHE CO.

2/16/99

Contract No: C201455
County: Ashe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)