

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
<u>PAVEMENT MARKINGS</u>			
<u>PAVEMENT MARKING LINES</u>			
		THERMOPLASTIC (4", 90 mils)	
TD	2FT. WHITE MINISKIP	3800 FT.	
TH	YELLOW SINGLE CENTER	3750 FT.	
TI	YELLOW DOUBLE CENTER	19300 FT.	
TC	10 FT. WHITE SKIP	1000 FT.	
TE	WHITE SOLID LANE LINE	37000 FT.	
TA	WHITE EDGELINE	2300 FT.	
			TOTAL 67150 FT.
		THERMOPLASTIC (8", 90 mils)	
TT	YELLOW DIAGONAL	550 FT.	
			TOTAL 550 FT.
		THERMOPLASTIC (24", 120 mils)	
T2	WHITE STOPBAR	220 FT.	
			TOTAL 220 FT.
<u>PAINT (4")</u>			
PD	2FT. WHITE MINISKIP	3800 FT.	
PH	YELLOW SINGLE CENTER	3750 FT.	
PI	YELLOW DOUBLE CENTER	19300 FT.	
PC	10 FT. WHITE SKIP	1000 FT.	
PE	WHITE SOLID LANE LINE	37000 FT.	
PA	WHITE EDGELINE	2300 FT.	
			TOTAL 67150 FT.
<u>PAINT (8")</u>			
TT	YELLOW DIAGONAL	1100 FT.	
			TOTAL 550 FT.
<u>PAINT (24")</u>			
T2	WHITE STOPBAR	440 FT.	
			TOTAL 220 FT.
<u>PAVEMENT MARKING SYMBOLS</u>			
THERMOPLASTIC THICK SYMBOL (90 mils)			
UA	LEFT TURN ARROW	41 EA.	
UB	RIGHT TURN ARROW	27 EA.	
UC	STRAIGHT ARROW	37 EA.	
UE	COMBO. STRAIGHT/ RIGHT	11 EA.	
			TOTAL 116 EA.
<u>PAINT SYMBOL</u>			
QA	LEFT TURN ARROW	41 EA.	
QB	RIGHT TURN ARROW	27 EA.	
QC	STRAIGHT ARROW	37 EA.	
QE	COMBO. STRAIGHT/ RIGHT	11 EA.	
			TOTAL 116 EA.
<u>PAVEMENT MARKING CHARACTER</u>			
THERMOPLASTIC THICK CHARACTER (120 mils)			
UI	ALPHANUMERIC CHARACTER	24 EA.	
			TOTAL 24 EA.
<u>PAINT CHARACTER</u>			
QI	ALPHANUMERIC CHARACTER	24 EA.	
			TOTAL 24 EA.
<u>PAVEMENT MARKERS</u>			
ME	YELLOW & YELLOW	570 EA.	
MF	CRYSTAL & RED	270 EA.	
			TOTAL 840 EA.

I5-FEB-2005 12:35
 \\lets-cg-fs01\TCU\2Grpup-MM\Resur-facing\Div03\wbs38224\38r\unswick\nc2\l_rdy_pm01r\021505.dgn
 psey@more AT TELC206427

APPROVED: _____	DATE: _____	PAVEMENT MARKING SCHEDULE	
SEAL	SCALE: NONE		
	DATE: _____		
	DWG. BY: _____		
	DESIGN BY: _____		
	REVIEWED BY: _____		
		REVISIONS	
		CADD FILE	