

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,800 CY		
0003	0106000000-E	230	BORROW EXCAVATION	2,600 CY		
0004	0264000000-E	SP	GENERIC GRADING ITEM GRADING PER SHOULDER MILE	0.2 SMI		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	111 TON		
0006	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	8 LF		
0007	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	409 LF		
0008	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	32 LF		
0009	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	517 LF		
0010	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	64 LF		
0011	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (30", 0.079")	16 LF		
0012	0995000000-E	340	PIPE REMOVAL	412 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	140 TON		
0014	1245000000-E	SP	SHOULDER RECONSTRUCTION	6.66 SMI		
0015	1330000000-E	607	INCIDENTAL MILLING	6,500 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,457 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	18,643 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,214 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,578 TON		
0020	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	30 TON		
0021	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	270 TON		
0022	2253000000-E	840	PIPE COLLARS	3 CY		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0024	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0025	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0026	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0027	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	350 LF		
0028	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	340 SY		
0029	2738000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE	30 SY		
0030	3030000000-E	862	STEEL BM GUARDRAIL	962.5 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	10 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	67,150 LF		
0037	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	550 LF		
0038	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	220 LF		
0039	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	24 EA		
0040	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	116 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	67,150 LF		
0042	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	550 LF		
0043	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	220 LF		
0044	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24 EA		
0045	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	116 EA		
0046	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	840 EA		
0047	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0048	6000000000-E	1605	TEMPORARY SILT FENCE	11,000 LF		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	144 LF		
0052	6084000000-E	1660	SEEDING & MULCHING	2 ACR		

C201422  
COUNTY: Brunswick County

2/16/99

Contract No: C201422  
County: Brunswick

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General