

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200841

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3030000000-E	862	512.5	LF	STEEL BM GUARDRAIL	5888000000-E	SP	230	LF	GENERIC UTILITY ITEM 20" HDPE WATER PIPE, SDR 9, 200 # WP BY DIRECTIONAL BORE
0043000000-N	226	Lump Sum		GRADING	3045000000-E	862	50	LF	STEEL BM GUARDRAIL, SHOP CURVED	6000000000-E	1605	1,900	LF	TEMPORARY SILT FENCE
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6006000000-E	1610	175	TON	STONE FOR EROSION CONTROL, CLASS A
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	6009000000-E	1610	675	TON	STONE FOR EROSION CONTROL, CLASS B
0080000000-E	SP	250	TON	CLASS IV SUBGRADE STABILIZA- TION	3215000000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6012000000-E	1610	475	TON	SEDIMENT CONTROL STONE
0134000000-E	240	160	CY	DRAINAGE DITCH EXCAVATION	3270000000-N	SP	7	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6015000000-E	1615	3	ACR	TEMPORARY MULCHING
0195000000-E	265	2,000	CY	SELECT GRANULAR MATERIAL	3380000000-E	862	412.5	LF	TEMPORARY STEEL BM GUARDRAIL	6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
0196000000-E	270	2,000	SY	FABRIC FOR SOIL STABILIZATION	3387000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
0199000000-E	SP	360	SF	TEMPORARY SHORING	3389100000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6024000000-E	1622	150	LF	TEMPORARY SLOPE DRAINS
0318000000-E	300	200	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3642000000-E	876	55	TON	PLAIN RIP RAP, CLASS A	6027000000-N	1622	5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0366000000-E	310	253	LF	15" RC PIPE CULVERTS, CLASS III	3649000000-E	876	55	TON	PLAIN RIP RAP, CLASS B	6030000000-E	1630	1,450	CY	SILT EXCAVATION
0372000000-E	310	360	LF	18" RC PIPE CULVERTS, CLASS III	3656000000-E	876	875	SY	FILTER FABRIC FOR DRAINAGE	6036000000-E	1631	2,210	SY	MATTING FOR EROSION CONTROL
0378000000-E	310	234	LF	24" RC PIPE CULVERTS, CLASS III	3659000000-N	SP	9	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6042000000-E	1632	300	LF	1/4" HARDWARE CLOTH
0384000000-E	310	454	LF	30" RC PIPE CULVERTS, CLASS III	4025000000-E	901	12	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	6070000000-N	SP	6	EA	SPECIAL STILLING BASINS
0576000000-E	310	234	LF	*** CS PIPE CULVERTS, ***** THICK (72", 138")	4025000000-E	901	10	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6084000000-E	1660	4	ACR	SEEDING & MULCHING
0582000000-E	310	224	LF	15" CS PIPE CULVERTS, 0.064" THICK	4072000000-E	903	95	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	6087000000-E	1660	1.5	ACR	MOWING
0654000000-E	310	78	LF	**** X **** CS PIPE ARCH CUL- VERTS, ***** THICK (142" X 92", 0.138")	4096000000-N	904	2	EA	SIGN ERECTION, TYPE D	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0708000000-E	310	92	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4102000000-N	904	2	EA	SIGN ERECTION, TYPE E	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0720000000-E	310	24	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4155000000-N	907	6	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4412000000-E	SP	132	SF	WORK ZONE SIGNS (STATIONARY)	6108000000-E	1665	3	TON	FERTILIZER TOPDRESSING
0808000000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4412100000-E	SP	176	SF	WORK ZONE SIGNS (PORTABLE)	6114000000-N	SP	4	HR	SPECIALIZED HAND MOWING
0995000000-E	340	706	LF	PIPE REMOVAL	4412200000-E	SP	154	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6117000000-N	1675	12	EA	RESPONSE FOR EROSION CONTROL
1220000000-E	545	75	TON	INCIDENTAL STONE BASE	4430000000-N	1130	100	EA	DRUMS	6123000000-E	1670	1	ACR	REFORESTATION
1297000000-E	607	180	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	4435000000-N	1135	20	EA	CONES					
1489000000-E	610	2,400	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4446100000-E	SP	174	LF	BARRICADES (TYPE III)					
1498000000-E	610	2,000	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	4450000000-N	1150	320	HR	FLAGGER					
1519000000-E	610	1,400	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4485000000-E	1170	80	LF	PORTABLE CONCRETE BARRIER					
1560000000-E	620	300	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4495000000-E	1170	200	LF	PORTABLE CONCRETE BARRIER (DRAINAGE)					
1693000000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4650000000-N	1251	163	EA	TEMPORARY RAISED PAVEMENT MARKERS					
2000000000-N	806	23	EA	RIGHT OF WAY MARKERS	4686000000-E	1205	4,310	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)					
2022000000-E	815	60	CY	SUBDRAIN EXCAVATION	4725000000-E	1205	8	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)					
2033000000-E	815	45	CY	SUBDRAIN FINE AGGREGATE	4810000000-E	1205	36,820	LF	PAINT PAVEMENT MARKING LINES (4")					
2044000000-E	815	250	LF	6" PERFORATED SUBDRAIN PIPE	4900000000-N	1252	80	EA	PERMANENT RAISED PAVEMENT MARKERS					
2055000000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	5255000000-N	1413	Lump Sum		PORTABLE LIGHTING					
2286000000-N	840	23	EA	MASONRY DRAINAGE STRUCTURES	5300000000-E	1505	25	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)					
2308000000-E	840	18.86	LF	MASONRY DRAINAGE STRUCTURES	5306000000-E	SP	25	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)					
2367000000-N	840	8	EA	FRAME WITH TWO GRATES, STD 840.29	5360000000-E	1510	59	LF	6" DI WATER PIPE, PC 350					
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5384000000-E	1510	236	LF	16" DI WATER PIPE, PC ***** (350)					
2374000000-N	840	5	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	5414000000-E	1510	60	LF	3/4" COPPER WATER PIPE, TYPE K					
2374000000-N	840	8	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5480000000-E	1510	1,035	LB	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP					
2484000000-E	SP	150	LF	GENERIC DRAINAGE ITEM CONCRETE VALLEY GUTTER	5648000000-N	1510	2	EA	RELOCATE EXISTING WATER METER					
2549000000-E	846	2,600	LF	2'-6" CONCRETE CURB & GUTTER	5666000000-E	1510	2	EA	FIRE HYDRANT, ***** WP (150)					
2556000000-E	846	1,580	LF	SHOULDER BERM GUTTER	5810000000-E	1530	450	LF	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI - WATER)					
2591000000-E	848	715	SY	4" CONCRETE SIDEWALK	5882000000-N	SP	1	EA	GENERIC UTILITY ITEM 16" GATE VALVE AND VALVE MAN- HOLE, 200#WP					
2598000000-E	848	90	SY	CONCRETE WHEELCHAIR RAMPS										
2830000000-N	858	1	EA	ADJUSTMENT OF MANHOLES										

5/28/199